
Shaping of uniform intensity profiles for single-site addressing of ^{85}Rb atoms

Strahlformung von homogenen Intensitätsprofilen zur Einzelplatzadressierung von ^{85}Rb-Atomen

Master thesis by Daniel Hagn

03.11.2026



TECHNISCHE UNIVERSITÄT DARMSTADT

ATOME - PHOTONEN - QUANTEN
Prof. Dr. Gerhard Birkl
Institut für Angewandte Physik
Fachbereich Physik

Shaping of uniform intensity profiles for
single-site addressing of ^{85}Rb atoms

Strahlformung von homogenen Intensitätsprofilen zur Einzelplatzadressierung von ^{85}Rb-Atomen

Master thesis by Daniel Hagn

1st reviewer: Prof. Dr. Gerhard Birkl
2nd reviewer: Lukas Sturm

Date of submission: 03.11.2026

Darmstadt

Cover image: A 3×3 grid of multi-tone Top Hat profiles generated using two orthogonally oriented Acousto-Optical Deflectors (AODs). Each profile is formed by the superposition of 3×4 individual Airy profiles, each corresponding to a beam diffracted by the AODs.

Contents

1 Introduction **1**

2 Theoretical Background **3**
2.1 Basics of Quantum Computation . . . 3
2.2 Trapping and Manipulation of Atomic Qubits . . . 5
2.2.1 Dipole Potentials for entrapping atoms . . . 5
2.2.2 Two-Photon Process . . . 6
2.2.3 Bloch Sphere and Single-Qubit Gate Operations . . . 7
2.2.4 Atomic properties and thermal motion of ^{85}Rb . . . 9
2.3 Acousto-optic deflection . . . 11
2.4 Top Hat profile generation . . . 12
2.4.1 Beam Shaper . . . 12
2.4.2 Multi-tone AOD . . . 14
2.4.3 Time-dependent interference . . . 16

3 Test Setup for generating Top Hat profiles with a Beam Shaper **19**
3.1 Magnification with a telescope . . . 19
3.2 Integration of two AODs . . . 23

4 Multi-tone Simulation for a Top Hat profile **27**
4.1 Simulation with an uniform distribution . . . 28
4.2 Atom-weighted simulation . . . 30
4.3 Combination of both simulations . . . 32
4.3.1 Beam Pointing relative to the Dipole Trap . . . 36
4.4 Comparison with a single spot . . . 37
4.4.1 Beam Pointing relative to the Dipole Trap . . . 40
4.5 Beating and Crest factor . . . 41
4.6 Pulse area with beating . . . 46
4.7 Validation with the test setup . . . 50
4.8 Conclusion . . . 54

5 Planning of an optical setup **57**

6 Conclusion and outlook **59**

Appendix **61**
A.1 The centering criterion . . . 61
A.2 Crest factor . . . 62
A.2.1 $N_x = 3$ and $N_y = 4$ tones . . . 64
A.3 Power of a normalized profile . . . 67

List of Abbreviations

AOD Acousto-Optical Deflector

AOM Acousto-Optical Modulator

CNOT controlled-NOT

DM Dichroic Mirror

DOE Diffractive Optical Element

EOM Electro-Optic Modulator

FBS Focal Beam Shaper

PBS Polarizing Beam Splitter

QUIPS Quantum Information Processing System

RF Radio Frequency

RMS Root Mean Square

1 Introduction

The technological advances of the the recent decades have led to a substantial increase in classical computing power. Nevertheless, specific computational problems, as those of combinatorial or logistical nature, remain intractable for classical computers within a reasonable amount of time. Quantum computers have the potential to solve specific classes of these problems more efficiently than classical computers. A prominent example is Shor's algorithm for the factorization of large numbers that illustrates the computational potential of quantum computers [1].

One approach to realizing a quantum processor involves neutral atoms trapped in registers of optical dipole traps that can be coherently manipulated using laser beams. The research group Atoms-Photons-Quanta of Prof. Birkl is pursuing this approach with the Quantum Information Processing System (QUIPS) experiment, which uses ^{85}Rb [2]. Using spatial light modulators and Acousto-Optical Deflectors (AODs), large two-dimensional atomic arrays containing up to a thousand atoms can be generated [3], while the Talbot effect can additionally enable the realization of three-dimensional structures, providing a pathway towards further scaling [4]. In this system, the hyperfine ground states $|F = 2\rangle$ and $|F = 3\rangle$ of $5^2S_{1/2}$ in ^{85}Rb are used to encode the qubit states $|0\rangle$ and $|1\rangle$, respectively.

Transitions between these states form the basis for the logical gate operations performed in this system. Of particular relevance to this thesis is the Raman laser system used to drive these transitions, which was developed and characterized in previous work [5] and subsequently integrated into the experimental setup [6]. The system is designed to provide the required light for two applications. In the first, the entire atomic plane is illuminated simultaneously, enabling transitions on a 40×40 grid of ^{85}Rb atoms [7]. At the time of this work, this setup is being commissioned and first tests are being conducted for experimental use. The second application is the single-site addressing of each atom, enabling optical transitions and, subsequently, logical operations to be performed locally.

A misalignment of the atom position regarding the focal point of the used laser, for example due to thermal fluctuations, can negatively affect the optical excitation and worsen the transition between the two logical states. To counter this issue, previously constructed optical systems have successfully demonstrated the use of uniform intensity profiles generated with an optical Beam Shaper for addressing the entire atomic plane [7, 8]. Building on these results, several approaches for generating locally uniform beam profiles are investigated and simulated during the course of this work with the aim of improving single-site addressing for the use in a new local Raman laser system.

The first approach uses an optical Beam Shaper [9]. Since the uniform illumination of the entire atomic grid has already shown promising results [7, 8], this approach investigates whether a similar concept can be applied locally to achieve uniform intensity profiles close to the diffraction limit. Another possibility is the superimposition of multiple individual deflected Gaussian beams to form a uniform beam profile. This method is based on an multi-tone AOD setup, which was first implemented for the movable optical tweezer [10]. For this new approach the influence of possible spatial and temporal interference is to be simulated in this work before any experimental use.

2 Theoretical Background

This chapter introduces the theoretical background required for the generation of uniform intensity profiles. It begins with the fundamentals of quantum computation as the underlying motivation, followed by an introduction to the relevant atomic physics and the optical components used in the experimental setup. Finally, the principles of optical beam shaping and the interference effects arising from the superposition of multiple optical fields are discussed.

2.1 Basics of Quantum Computation

To perform information processing based on quantum states, a system has to fulfill a certain kind of criteria. In 2000, David P. DiVincenzo defined five such criteria that a physical system must fulfill in order to realize quantum computers [11].
The fundamental unit of information in a classical computer is the bit, which can either take the value zero or one. Its counterpart in a quantum computer is the so-called quantum bit, or qubit. Qubits are physical two-level systems with the possible states $|0\rangle$ and $|1\rangle$, which exist in a superposition $|\Psi\rangle = a\,|0\rangle + b\,|1\rangle$ of both states and are subject to the normalization condition $|a|^2 + |b|^2 = 1$. While the states of a single qubit form a two-dimensional complex vector, N qubits result in a 2^N-dimensional vector. A physical system consisting of such qubits must be adequately characterized, which means that the Hamiltonian operator $\hat{H}$ and all energy levels must be sufficiently well characterized with respect to possible couplings between internal states, other qubits and external fields. If such couplings are unknown, errors may occur that reduce the fidelity of information processing. To achieve sufficient computational power, the physical system must be scalable, making scalability a central focus of research.
As in classical computing, a quantum computation requires a well-defined initial state. Therefore, all qubits must be initialized in a known reference state, which can be achieved, for example, through laser cooling and optical pumping.
Decoherence characterizes the dynamics of qubits under environmental influences. It is the loss of phase information required for quantum interference and, consequently, can reduce the computational advantage of a quantum computer over a classical computer when solving certain problems. If the gate operation time is significantly shorter than the decoherence time, the quantum coherence can be maintained throughout the computation, allowing the computational advantages of quantum information processing to be preserved.
Gate operations form the central building block of quantum computation and consist of sequences of unitary transformations U_i. A distinction is made between single-qubit gate operations, which are performed on only one qubit and multi-qubit gate operations, which act on multiple qubits simultaneously. A quantum computer requires a universal set of quantum gates, consisting of a complete set of single-qubit gate operations and one two-qubit gate operation, such as the controlled-NOT (CNOT) gate [12]. A CNOT gate flips the state of the target qubit depending on the state of the control qubit according to:

$$|00\rangle \rightarrow |00\rangle\,, \qquad |01\rangle \rightarrow |01\rangle\,,$$
$$|10\rangle \rightarrow |11\rangle\,, \qquad |11\rangle \rightarrow |10\rangle\,.$$

Gate operations are only supposed to act on qubits for a specific amount of time t, which can be achieved using focused laser pulses of appropriate duration.
At the end of a calculation the result has to be read out. Assuming that the density matrix of a qubit has the form $\rho = p\,|0\rangle\langle 0| + (1-p)\,|1\rangle\langle 1| + \alpha\,|0\rangle\langle 1| + \alpha^*\,|1\rangle\langle 0|$, the measurement should yield $|0\rangle$ with probability p and $|1\rangle$ with probability $1-p$. This measurement destroys the superposition of the two states of the measured qubit and projects it onto one of the two eigenstates. A method for measuring the qubit state is fluorescence imaging. By applying additional laser light, a transition is driven for one of the two qubit states, causing it to emit photons through spontaneous emission, while the other state remains dark.
In addition to these five criteria, two further criteria have been defined that address the ability to exchange quantum information between different computing units, thereby enabling the realization of quantum networks [11]. Atom transport within an atomic grid can be achieved using movable optical tweezers, as demonstrated, for example, in [10]. However, transporting these stationary qubits, used for the actual computation, over long distances while preserving their coherence is challenging. The ability to convert stationary qubits into “flying” qubits and vice versa would enable the transmission of quantum information over such distances. A possible realization of a flying qubit is a photon, which can encode quantum information in properties such as its phase or polarization.

2.2 Trapping and Manipulation of Atomic Qubits

One physical system suitable for the implementation of a quantum processor consists of neutral atoms trapped in optical dipole traps and manipulated by laser light. Atoms are identical physical systems and can therefore be collectively cooled and addressed. Coherence times of neutral atoms in the range of seconds are possible and result from the long life times of stable atomic energy levels.

2.2.1 Dipole Potentials for entrapping atoms

The method to trap neutral atoms for further experiments is the use of high intensity laser beams to create optical dipole traps as done in [13]. The atom itself is hereby simplified to be a two level quantum system consisting of a ground state $|g\rangle$ and an excited state $|e\rangle$. An incident light field can induce oscillations between the two levels with a Rabi frequency Ω_0 [12] given by:

$$\Omega_0 = \frac{\langle g| \hat{\mathbf{d}} \cdot \mathbf{E} |e\rangle}{\hbar}. \tag{2.1}$$

The light field with the energy $\hbar\omega_{\text{light}}$ is detuned to the atomic resonance by $\Delta = \omega_0 - \omega_{\text{light}}$. The coupling of the light field and the atomic states lead to a shift of the eigenvalues of their energy by:

$$E_{\pm} = -\frac{\hbar\Delta}{2} \pm \frac{\hbar\Omega}{2}. \tag{2.2}$$

Ω is the generalized Rabi frequency and is dependent of the detuning and the Rabi frequency of the transition with:

$$\Omega := \sqrt{\Omega_0^2 + \Delta^2}. \tag{2.3}$$

A schematic drawing of the uncoupled and coupled system is shown in Figure 1. The energy shift resulting from the incident laser beam leads to an effective potential in the focal plane that is given by:

$$U_{\text{dip}}(\mathbf{r}) = \frac{3\pi c^2}{2\omega_0^3} \frac{\Gamma}{\Delta} I(\mathbf{r}). \tag{2.4}$$

Whether the potential is attractive or repulsive depends on the sign of the detuning Δ. The potential created by a red-detuned light field ($\Delta < 0$) is attractive for the ground state, thereby enabling the trapping of atoms. For the excited state such a potential is repulsive and ensures no trapping in an unwanted state. By tuning the frequency of the light field, the sign of the detuning can be reversed, thereby changing the character of the potential. When a light field interacts with an atom, spontaneous emission can lead to photon scattering. These scattering events cause changes in the momentum of the atom, leading to heating and potentially to atom loss. For a large detuning Δ, the trapping potential dominates over the scattering rate:

$$\Gamma_{\text{SC}} = \frac{3\pi c^2}{2\hbar\omega_0^3} \left(\frac{\Gamma}{\Delta}\right)^2 I(\mathbf{r}), \tag{2.5}$$

which enables the trapping despite the heating character of spontaneous photon scattering.




Fig. 1: (a):Energy level scheme for a two-level system. (b): Scheme for the Dressed States of a two-level system interacting with a light beam. Taken from [14] and upscaled using AI tools (Claude Opus 5, Anthropic).

2.2.2 Two-Photon Process

For ^{85}Rb the basis of every logical operation is a two-photon process. The coupling of the two qubit states $|0\rangle := |g\rangle$ and $|1\rangle := |e\rangle$ is achieved in a two-photon process involving a third intermediate state $|i\rangle$ in a λ-scheme as shown in Figure 2. Hereby each level $|k\rangle$ with its energy $\hbar\omega_k$ interacts with the incoming light described by an classical electric field of two frequency components $\omega_{1,2}$ which are stable in their relative phases $\phi_{1,2}$:

$$\mathbf{E} = \mathbf{E_1}\cos(\omega_1 t + \phi_1) + \mathbf{E_2}\cos(\omega_2 t + \phi_2).$$

The light matter interaction is described with the dipole operator $\hat{\mathbf{d}}$ resulting in the following Hamiltonian for the three level system:

$$\hat{H} = \hbar\omega_e\,|e\rangle\langle e| + \hbar\omega_i\,|i\rangle\langle i| + \hbar\omega_g\,|g\rangle\langle g| - \hat{\mathbf{d}}\cdot\mathbf{E}. \tag{2.6}$$

The frequency difference between the two qubit states $\omega_{eg} = \omega_1 - \omega_2 - \delta$ for ^{85}Rb is approximately 3.035 GHz. A laser setup for generating this difference with an Electro-Optic Modulator (EOM) was built [5] and further developed [6] and can now be used to address all atoms in the atomic plane at once [7]. The Rabi frequency for each level is given by

$$\Omega_g = \frac{\langle g|\,\mathbf{d}\cdot\mathbf{E_1}\,|i\rangle}{\hbar} \tag{2.7a}$$

$$\Omega_e = \frac{\langle e|\,\mathbf{d}\cdot\mathbf{E_2}\,|i\rangle}{\hbar} \tag{2.7b}$$

If the detuning Δ relative to the intermediate state $|i\rangle$ is much larger than the individual frequencies ω_e and ω_g, then no population gathers in the intermediate state $|i\rangle$ and it can be adiabatically eliminated [12]. The system can therefore be approximated as a two-level system




Fig. 2: Schematic of a two-photon process in a λ scheme used for coupling the qubit states [5].

described by the new Hamiltonian:

$$\hat{H} = -\hbar \begin{pmatrix} \frac{|\Omega_g|^2}{4\Delta} & \frac{\Omega_{\text{eff}}^*}{2} \\ \frac{\Omega_{\text{eff}}}{2} & \frac{|\Omega_e|^2}{4\Delta} \end{pmatrix}.$$

The effective Rabi frequency for this two-photon process is then given by:

$$\Omega_{\text{eff}} = \frac{\Omega_e^* \Omega_g}{2\Delta}, \tag{2.8}$$

and is therefore dependent on the detuning of the laser light and the Rabi frequencies of the single-photon processes. The single-photon Rabi frequencies are themselves proportional to the electric field and thus proportional to the square root of the laser intensity.

2.2.3 Bloch Sphere and Single-Qubit Gate Operations

To realize a Quantum Computer, a universal set of quantum gate operations is needed. Such a universal set consists of a complete set of single-qubit gate operations and one entangling two-qubit gate such as a CNOT [12]. Important single qubit gate operations are the following:

$$X = \begin{pmatrix} 0 & 1 \\ 1 & 0 \end{pmatrix} \quad Y = \begin{pmatrix} 0 & -i \\ i & 0 \end{pmatrix} \quad Z = \begin{pmatrix} 1 & 0 \\ 0 & -1 \end{pmatrix} \quad H = \frac{1}{\sqrt{2}} \begin{pmatrix} 1 & 1 \\ 1 & -1 \end{pmatrix}. \tag{2.9}$$

To visualize single-qubit gate operations in a two-level quantum system, the model of the Bloch sphere, including the Bloch vector, can be used. A quantum state $|\Psi\rangle$ is represented as a Bloch vector by the spherical coordinates r, Θ, and φ. The length of the Bloch vector r is conserved in undamped systems and, due to the normalization of quantum states, satisfies $|\Psi|^2 = r^2 = 1$. The polar angle Θ specifies the relative proportions of the ground states $|0\rangle$ and $|1\rangle$ and depends directly on the duration of the incident laser radiation, which causes the population of the ground states to change. For $\Theta = 0$, $|\Psi\rangle = |0\rangle$, and for $\Theta = \pi$, $|\Psi\rangle = |1\rangle$. The azimuth angle φ specifies the axis of rotation of the Bloch vector as the population in the two ground states changes and can be adjusted via the phase of the two photons involved in the two-photon process [12]. A visualization of the Bloch sphere is shown in Figure 3. The general form of a Bloch vector is:

$$|\Psi\rangle = \cos(\Theta/2)\,|0\rangle + e^{i\varphi} \sin(\Theta/2)\,|1\rangle\,. \tag{2.10}$$

Single qubit gate operations can generally be represented as rotations of the Bloch vector. In a given basis $|0\rangle = \begin{pmatrix} 1 \\ 0 \end{pmatrix}$ and $|1\rangle = \begin{pmatrix} 0 \\ 1 \end{pmatrix}$ the gate operations can be written as:

$$\hat{R}(\Theta, \varphi) = \begin{pmatrix} \cos(\Theta/2) & -ie^{-i\varphi}\sin(\Theta/2) \\ -ie^{i\varphi}\sin(\Theta/2) & \cos(\Theta/2) \end{pmatrix}. \tag{2.11}$$

For $\Theta = \pi$ the initial qubit state is flipped and gathers additional phase depending on the phase φ of the laser:

$$\hat{R}(\pi, \varphi)\,|0\rangle = -ie^{-i\varphi}\,|1\rangle \quad \hat{R}(\pi, \varphi)\,|1\rangle = -ie^{i\varphi}\,|0\rangle\,.$$

For $\varphi = 0$ this is effectively the realization of an X gate with an additional phase factor: $\hat{R}(\pi, 0) = -iX$, while for $\varphi = \pi/2$ the Y gate is created: $\hat{R}(\pi, \pi/2) = -iY$. A Z gate can be realized by a combination of different laser pulses:

$$\hat{R}_z(\pi) = -iZ = \hat{R}(\pi/2, 0) \cdot \hat{R}(\pi, \pi/2) \cdot \hat{R}(-\pi/2, 0). \tag{2.12}$$

A 2π-pulse with $\Theta = 2\pi$ returns the Bloch vector to its initial position but introduces a global phase in the quantum state with a shifted sign:

$$\hat{R}(2\pi, \varphi)\,|0\rangle = -\,|0\rangle \quad \hat{R}(2\pi, \varphi)\,|1\rangle = -\,|1\rangle\,.$$




Fig. 3: Schematic representation of the Bloch sphere. Single qubit gate operations result in a rotation (red) along paths (blue) on the surface of the sphere and allow to create superpositions of both states [15].

2.2.4 Atomic properties and thermal motion of ^{85}Rb

The Quantum Information Processing System (QUIPS) experiment uses ^{85}Rb atoms trapped in optical dipole potentials for quantum information processing. Its energy level structure [2] is particularly well-suited for the implementation of a quantum processor since the required transition wavelengths can be generated using conventional laser systems. The hyperfine ground state $|F = 2, m_F = 0\rangle$ of the ground state $5^2S_{1/2}$ is the qubit state $|0\rangle$, while the state $|1\rangle$ is represented by the state $|F = 3, m_F = 0\rangle$. A CNOT gate with ^{85}Rb can be realized with a two-photon process using the wavelengths 420 nm and 1012 nm through a process called Rydberg Blockade, as demonstrated in [14]. Single-qubit gate operations need a wavelength of 795 nm or 780 nm in a two-photon process depending on whether the D_1 or D_2 line is used for the transition. The D_1 line of ^{85}Rb is shown in Figure 4. According to the frequency splitting, the two photons participating in the logical operation need to have a frequency difference of approximately 3.035 GHz.
To describe one atom inside an optical dipole trap, the model of a thermal harmonic oscillator [12] can be used. The wavefunction Ψ_n for a level n of the harmonic oscillator is given by:

$$\Psi_n(x) = \frac{1}{\sqrt{2^n n!}\pi^{\frac{1}{4}}\sqrt{a}} H_n\left(\frac{x}{a}\right) e^{\frac{-x^2}{2a^2}}. \tag{2.13}$$

$a = \sqrt{\frac{\hbar}{m\omega}}$ is the characteristic length of the harmonic oscillator and $H_n\left(\frac{x}{a}\right)$ are the Hermite Polynomials. The temperature T of the thermal state in combination with the frequency of the dipole trap $\omega = 2\pi\nu$ determines the average quadratic distance of the atom to the center of the trap:

$$\sigma^2 = \frac{\hbar}{2m\omega} \coth\left(\frac{\hbar\omega}{2k_BT}\right). \tag{2.14}$$

The spatial probability density $Pd = |\Psi|^2$ of the atom is given by a Gaussian distribution:

$$Pd(x, y, z) = \frac{1}{(2\pi)^{\frac{3}{2}}\sigma_x\sigma_y\sigma_z} e^{-\frac{x^2}{2\sigma_x^2} - \frac{y^2}{2\sigma_y^2} - \frac{z^2}{2\sigma_z^2}} \tag{2.15}$$

For a symmetric dipole trap in the two-dimensional atomic plane, the equation simplifies to:

$$Pd_{2D}(r, \varphi) = \frac{1}{2\pi\sigma^2} e^{\frac{-r^2}{2\sigma^2}}. \tag{2.16}$$

With this probability density it is possible to effectively calculate the region of interest in which a single atom can be found. This is of further interest for single-site addressing when measuring whether an atom is uniformly illuminated with a laser beam profile. Taking the atomic positions into account for single-site addressing also enables simulations of atom displacement, allowing the suitability of different beam profiles to be evaluated.
By integrating over the area, the probability $P(r \leq R)$ of finding the atom within a radius R is given by:

$$P(r \leq R) = \int_0^{2\pi} \int_0^R Pd_{2D}(r, \varphi) r dr d\varphi = 1 - e^{-\frac{R^2}{2\sigma^2}}. \tag{2.17}$$

Within a radius of $R = 3\sigma$ the probability to find the atom is $P(r \leq 3\sigma) = 98.89\%$




Fig. 4: Hyperfine structure of the D_1 line of ^{85}Rb with the frequency splittings between the hyperfine energy levels in different units and the g-factor for each level. The ground state $5^2S_{1/2}$ with its splitting is used for quantum information processing [2].

2.3 Acousto-optic deflection

In this work, a new optical setup for the single-site addressing of ^{85}Rb atoms for single-qubit gate operations, referred to as Raman tweezers, is to be simulated, designed and tested. Afterwards, an optical system combining this new local addressing scheme with an global Raman laser system is to be built. While the global setup reproduces the system developed in [7], using a Beam Shaper as its defining optical component, the local setup includes an Acousto-Optical Deflector (AOD) for single-site addressing, as demonstrated in [10].
When an Radio Frequency (RF) signal is applied to an AOD crystal, it induces a sound wave and, consequently, a periodic variation of the refractive index Δn [16]. The wavelength $\Lambda = \frac{v}{f_s}$ of this acoustic wave is determined by the speed of sound v in the medium and the RF frequency f_s of the applied signal This sound wave acts like a static diffraction grating on radiation propagating through the crystal, since the variations in the refractive index have a significantly longer wavelength than the light $\Lambda \gg \lambda$. Diffraction at an angle Θ_B occurs if the Bragg condition is fulfilled [17]:

$$\sin(\Theta_B) = \frac{\lambda}{2\Lambda} = \frac{\lambda f_s}{2v}. \tag{2.18}$$

Thus, selecting a specific frequency results in a corresponding deflection angle, allowing different regions of the target plane to be selectively illuminated. A schematic representation of this condition is shown in Figure 5. The diffraction efficiency of an AOD is defined as the ratio




Fig. 5: Schematic drawing of the Bragg interference in an AOD [18]. The incident light beam is diffracted at the Bragg angle Θ_B, resulting in a deflection angle of $2\Theta_B$.

if the diffracted intensity I_d and the incident intensity I as $\eta = \frac{I_d}{I}$. The first-order diffracted laser beam experiences a frequency and wave-vector shift due to energy and momentum conservation:

$$\omega_j = \omega + \Omega_j, \quad k_j = k + q_j. \tag{2.19}$$

In a multi-tone setup multiple acoustic waves are generated inside the AOD crystal resulting in different gratings and therefore diffracted beams. The variation of the refractive index in this case can be written as a sum over all N sound waves:

$$\Delta n = -\Delta n_0 \sum_{j=1}^{N} \sqrt{\kappa_j} \exp\left(i(\Omega_j t - \vec{q}_j \cdot \vec{r})\right) + \text{c.c} \tag{2.20}$$

For all N waves a normalization condition must hold true for the power ratios κ_j:

$$\sum_j \kappa_j = 1$$

2.4 Top Hat profile generation

The fidelity of quantum gate operations can be increased by using a uniform laser beam profile. In practice, the Gaussian intensity profile of the Raman tweezers can be transformed into a Top Hat profile, providing a more uniform intensity across the addressed atomic array. This reduces the sensitivity to errors in the calibration of the relative position between the dipole traps and the Raman tweezers, thereby reducing power fluctuations and, consequently, Rabi-frequency fluctuations.
To quantify the flatness of a Top Hat intensity profile, the uniformity U is defined as:

$$U = \frac{\Delta I}{\langle I \rangle}, \tag{2.21}$$

where ΔI denotes the standard deviation of the intensity and $\langle I \rangle$ its mean value. A smaller value of U indicates a more uniform intensity distribution, with $U = 0$ corresponding to an ideally uniform profile. The aim of optical beam shaping is therefore to minimize ΔI while keeping the mean intensity $\langle I \rangle$ approximately constant.
To estimate the extent to which laser radiation from neighboring positions in the grid is emitted into the central position and potentially reduces the fidelity of gate operations, the crosstalk η can be defined. It is given as the ratio of the power of the nearest neighbors P_{NN} in the target area to the power of the central structure P_0 in the target area:

$$\eta = \frac{P_{\mathrm{NN}}}{P_0}. \tag{2.22}$$

The power of the central structure P_0 represents the desired laser power of the central beam profile at the atom's position, while P_{NN} denotes the unwanted light illuminating the atom. The number of considered nearest neighbors when evaluating the crosstalk depends on the structure of the atomic grid. For a Cartesian grid, the eight nearest neighbors are included in the ratio η, whereas a hexagonal grid would include six nearest neighbors. Considering all possible nearest neighbors provides an upper bound for the crosstalk and thus represents the worst-case scenario for unwanted light. In practice, the measured crosstalk is expected to be lower than the simulated values. A key challenge for generating Top Hat profiles for effective single-site addressing of individual qubits is to minimize the uniformity U while keeping the crosstalk η low. During the course of this work two methods are examined and analyzed for generating local Top Hat profiles in regards of their compatibility with the already running experimental setup.

2.4.1 Beam Shaper

A Beam Shaper is an optical component that can be used to transform a laser beam profile into a desired form based on the incident beam profile and the properties of the Beam Shaper itself. A refractive beam shaper modifies the intensity distribution of a beam by changing its propagation direction through refraction. Specially designed optical surfaces redistribute the laser beam such that regions with high intensity are expanded, while regions with lower intensity are compressed. Since the transformation is achieved through the geometry of the optical surfaces, most of the incident optical power remains in the desired beam.
A diffractive Beam Shaper uses a spatially varying optical phase to modify the propagation of the incident beam. Such a Beam Shaper can implemented as a Diffractive Optical Element

(DOE) with a structured surface that determines the local phase shift. To generate a uniform intensity profile, a focusing lens must additionally be placed behind the diffractive Beam Shaper [19], forming the Focal Beam Shaper (FBS). The resulting field $E_f(x_f, y_f)$ in the focal plane of the focusing lens can be paraxial approximated as the Fourier transform of the incident field $E_0(x, y)$ modulated by the transfer function of the Beam Shaper T_{FBS} [20]:

$$E_f(x_f, y_f) = \mathcal{FT}[E_0(x, y) \cdot T_{\text{FBS}}(x, y)]. \tag{2.23}$$

The transfer function for the FBS is given by the phase modulation $T_{\text{FBS}} = e^{i\phi_{\text{FBS}}(x,y)}$. A schematic of the beam path of an FBS is shown in Figure 6.
In previous works [7, 8], a Beam Shaper in combination with a focusing lens was used to create a rectangular Top Hat profile in the atomic plane capable of dressing the whole ^{85}Rb array, consisting of more than 40×40 atoms with a pitch of 5.288 µm. During this work such an approach is tested near the diffraction limit in which a beam profile resembling a Super Gaussian function is created with the goal to minimize the uniformity and the crosstalk. For a local approach the created Top Hat profile has to be projected to every atom site in the atomic plane. Thus, in addition to generating the Top Hat profile with the desired uniformity and crosstalk, the deflection process must also preserve the beam quality. As already discussed, the method of single-site addressing is realized with an AOD. The deflection of a Gaussian beam through the sound wave within the crystal of the AOD changes the frequency ω and the k-vector $\vec{k}$. The acousto-optical crystal additionally imposes a spatially dependent phase on the Gaussian beam because the acoustic wave takes a finite time to propagate through the crystal and therefore interacts with different parts of the beam at different times. Additionally, these crystals are cut such that different parts of a wide beam experience different optical path lengths and therefore different phases. For these reasons the AOD potentially introduces a new, unknown transmission function $T_{\text{AOD}}(x, y)$. The resulting field $E_f(x_f, y_f)$ is then given by:

$$E_f(x_f, y_f) = \mathcal{FT}[E_0(x, y) \cdot T_{\text{AOD}}(x, y) \cdot T_{BS}(x, y)].$$

In the case of $T_{\text{AOD}}(x, y) \neq 1$, the Top Hat profile can be distorted or even destroyed entirely, resulting in Airy spots in the atomic plane and thus eliminating the advantage over previously developed setups using Gaussian spots [18].




Fig. 6: Schematic beam path of a FBS. The Gaussian input beam (profile shown on the left) passes through the FBS, which imprints a phase modulation, and is then focused by a lens of focal length F. In the focal plane, a Top Hat intensity profile forms on the screen. Taken from Fig. 2 of [19] and upscaled using AI tools (Claude Opus 5, Anthropic).

2.4.2 Multi-tone AOD

Another approach for the generation of uniform intensity profiles uses an AOD. The basic concept consists of superimposing multiple deflected laser beams to generate a uniform laser intensity profile. Each spot is generated by the AOD in a multi-tone configuration, where the RF signal consists of multiple frequency components f_s, with each component corresponding to one spot. The incident laser beam in front of the AOD and the spots within the atomic plane can be described as a Gaussian beam:

$$I_g(r) = I_0 \exp\left[-2(r - r_c)^2/(\omega^2)\right]. \tag{2.24}$$

ω is the beam waist defined as the beam distance from the center r_c where the intensity has decreased to $I_0/e^2 \approx 13.5\% I_0$. Parameters for optimizing the uniformity of a Top Hat profile are the beam waist in the atomic plane and the distance between each individual spot, determined by the optical setup. The waist within the atomic plane is a projection of the beam waist in front of the AOD. So varying the used magnifying optics is a way change the uniformity. The distance between each individual spot is determined by the angle of deflection created by the AOD and thus by the used RF frequency as well as the following imaging optics. During the course of this work, another type of beam profile has to be considered for beam sizes approaching the diffraction limit. An Airy profile, described by a first-order Bessel function J_1, is used to model the individual spots in the atomic plane, as it reproduces the side structures observed in [10], which do not appear for a Gaussian beam profile:

$$I_a(r) = I_0 \left[\frac{2J_1(kr)}{kr}\right]^2. \tag{2.25}$$

The Bessel function is parametrized such that its central peak has the same waist ω as the Gaussian function. $k \cdot r_0 = 3.8317$ is the first zero of the first-order Bessel function. Matching the waists of the two profiles yields $r_0 \approx 1.483\omega$. A visualization of this parametrization is shown in Figure 7.




Fig. 7: Plot of a Gaussian curve and an Airy function used for the parametrization of single laser spot profile in the atomic plane. The Airy profile is parametrized with the same waist ω for its central peak as the Gaussian profile.

When multiple coherent laser beams are superimposed interference occurs. Because of the imposed frequency shift of the AOD, vertically or horizontally neighboring overlapping spots do not spatially interfere. Along the anti-diagonals of the grid, the frequency shifts are identical, resulting in spatial interference. For example, a base frequency of 100 MHz is chosen with a frequency span of 1 MHz in each dimension. For eleven spots per dimension, this results in a frequency spacing of 0.1 MHz between adjacent spots. The frequency 200.3 MHz can be obtained from different combinations of frequency shifts along the two deflection axes, such as 0.1 MHz + 0.2 MHz or 0.2 MHz + 0.1 MHz. A visual representation of the interfering spots is shown in Figure 8 on the left. For intensity profiles with different offset frequencies, such as 100 MHz along the x-axis and 105 MHz along the y-axis, this problem does not occur on the anti-diagonals of the profile. A method to avoid spatial interference is to choose a different number of tones per axis with an identical frequency width.
One approach is the use of $N_x = N$ and $N_y = N + 1$ tones. In this case, the resulting profile remains symmetric, and only one pair of spots on opposing edges of the profile experience the same frequency shift, as illustrated on the right in Figure 8. The condition for the selection of the waist ω and the frequency width W in µm of such a profile that limits spatial interference is given by:

$$\sqrt{d^2 + d^2} = \sqrt{2}d > 2\omega. \tag{2.26}$$

Once no overlap of these spots is ensured the matter of unwanted spatial interference poses no limiting problem for the generation of uniform intensity profiles. A more general discussion of projections of two-dimensional light patterns with an AOD regarding interference can be found in [21].
Since the profile generation involves the superposition of coherent laser beam profiles with closely spaced frequencies, time-dependent interference, also known as beating, must also be taken into account. Beating can pose as a limiting factor for the efficient single-site addressing by disrupting Rabi oscillations and therefore single qubit gate operations. The beating frequency can be estimated from the frequency difference between neighboring spots, which typically lies in the kHz to MHz range.




Fig. 8: Left: Representation of a $4 \cdot 4$ spot grid. Spots with the same frequency shift that can spatially interfere are marked with the same color. Right: Using different numbers of tones (here 3×4) leaves just one pair of spots with the same frequency and reduces interference. Adapted from Fig. 3 of [22] with labels and annotations removed using AI tools (Claude Opus 5, Anthropic).

2.4.3 Time-dependent interference

During this work a simulation is conducted to determine the scale of the time-dependent interference for the multi-tone AOD setup. The optical fields within the simulation are treated using a standard complex-field description of coherent light, in which the total field is calculated as a superposition of the individual fields and the intensity is proportional to the squared absolute value of the resulting field [23].
Both AODs shift the optical frequency. A spot $s = (i, j)$, produced by tone i of the x-AOD and tone j of the y-AOD, thus has the frequency:

$$f_s = f_{x,i} + f_{y,j}, \qquad f_{x,i} = f_{\mathrm{x,0}} + W\frac{i}{N_x - 1}, \quad f_{y,j} = f_{\mathrm{y,0}} + W\frac{j}{N_y - 1}. \tag{2.27}$$

W denotes the frequency width of the generated spots, which is equal for both dimensions as discussed above. $f_{(\mathrm{x,y}),0}$ is the offset frequency of the respective AOD dimension and $N_{x,y}$ denotes the corresponding number of spots. The electric fields of the spots are superimposed rather than their intensities to take interference effects into account. For each spot s the spatial field amplitude is given by:

$$g_s(\mathbf{r}) = \sqrt{a_s}\, u(\mathbf{r} - \mathbf{c}_s), \qquad a_s = a_{x,i}\, a_{y,j}, \tag{2.28}$$

where u is the real mode in the focal plane, normalized to $u(\mathbf{0}) = 1$ (Gaussian e^{-r^2/w^2} or Airy $2J_1(kr)/(kr)$), $\mathbf{c}_s$ is the position of each spot in the focal plane and $a_{x,i}$, $a_{y,j}$ are intensity weights. In the linear regime of the AOD the diffraction efficiency is proportional to the RF power, so a is an RF power ratio and $\sqrt{a}$ the corresponding RF voltage ratio. The spot phase is the sum of the two tone phases of each AOD:

$$\phi_s = \phi_{x,i} + \phi_{y,j}, \tag{2.29}$$

so only $N_x + N_y$ of the $S = N_x \cdot N_y$ spot phases are free parameters. Only differences of spot frequencies are relevant for the analysis of the time-dependent interference. If all differences are integer multiples of a fundamental frequency f_0 (their greatest common divisor), every spot frequency can be written as

$$f_s = f_{\mathrm{min}} + k_s f_0, \qquad k_s = \frac{f_s - f_{\mathrm{min}}}{f_0} \in \mathbb{N}_0. \tag{2.30}$$

Hereby $f_{\mathrm{min}} = f_{\mathrm{x,0}} + f_{\mathrm{y,0}}$ holds. The fundamental frequency can be calculated through:

$$f_0 = \frac{W}{\mathrm{lcm}(N_x - 1,\, N_y - 1)}, \qquad T_0 = \frac{1}{f_0}. \tag{2.31}$$

For a 3×4 grid this results in $f_0 = W/6$. The index s, as introduced above, labels a spot and k_s its so called frequency order. Spots with the same order form the group:

$$\mathcal{S}_m = \{\, s : k_s = m \,\}. \tag{2.32}$$

The superposition of all spot profiles with their respective phases ϕ_s defines the time-independent electric field, referred to as the group field:

$$H_m(\mathbf{r}) = \sum_{s \in \mathcal{S}_m} g_s(\mathbf{r})\, e^{i\phi_s}. \tag{2.33}$$

The time-dependent electric field of a single spot on the other hand is then given by:

$$E_s(\mathbf{r},t) = g_s(\mathbf{r})e^{i\phi_s}e^{i2\pi f_s t} = e^{i2\pi f_{\min} t} g_s(\mathbf{r})e^{i\phi_s}e^{i2\pi k_s f_0 t}. \tag{2.34}$$

For the total field, obtained by summing over all spots, the definition of the group field can therefore be used:

$$E(\mathbf{r},t) = \sum_s E_s(\mathbf{r},t) = e^{i2\pi f_{\min} t} \sum_m H_m(\mathbf{r})\, e^{i2\pi m f_0 t}. \tag{2.35}$$

Since later only the squared absolute value $|E(\mathbf{r},t)|^2$ is of interest, the common phase factor $e^{i2\pi f_{\min} t}$ can be neglected. The time-dependent field can therefore be expressed as a superposition of monochromatic frequency components, following the standard Fourier description of polychromatic optical fields [23]:

$$E(\mathbf{r},t) = \sum_m H_m(\mathbf{r})\, e^{i2\pi m f_0 t}. \tag{2.36}$$

The intensity is then given by:

$$I(\mathbf{r},t) = |E(\mathbf{r},t)|^2 = \sum_d D_d(\mathbf{r})\, e^{i2\pi d f_0 t}, \tag{2.37}$$

which is a trigonometric polynomial with the Fourier coefficients $D_d(\mathbf{r})$ and the beat frequencies $f_{\text{beat}} = d f_0$. The parameter d is hereby called the beating order and is defined as the difference in the spot orders $k_{s,s'}$ of the overlapping spots with $s = (i,j)$ and $s' = (i',j')$:

$$d = k_{i,j} - k'_{i',j'} = 3\,\Delta i + 2\,\Delta j. \tag{2.38}$$

The Fourier coefficients are calculated in terms of the group fields and the spots as:

$$D_d(\mathbf{r}) = \sum_{m-n=d} H_m(\mathbf{r}) H_n^*(\mathbf{r}) = \sum_{k_s - k_{s'}=d} g_s(\mathbf{r})\, g_{s'}(\mathbf{r})\, e^{i(\phi_s - \phi_{s'})}. \tag{2.39}$$

Because $I^*(t) = I(t)$ holds true, the Fourier coefficients fulfill:

$$D_{-d} = D_d^*, \qquad D_0 \in \mathbb{R}. \tag{2.40}$$

Calculating the time average of the intensity over one time period T_0 leaves only the term $d = 0$:

$$\langle I(\mathbf{r},r)\rangle_t = \frac{1}{T_0}\int_0^{T_0} \sum_d D_d(\mathbf{r})\, e^{i2\pi d f_0 t} = D_0(\mathbf{r}) = \sum_m |H_m(\mathbf{r})|^2\,. \tag{2.41}$$

This result can be expressed in terms of the spatial field amplitudes:

$$\langle I(\mathbf{r},r)\rangle_t = \underbrace{\sum_s g_s^2(\mathbf{r})}_{\text{incoherent sum}} + 2 \sum_{\substack{s<s' \\ k_s = k_{s'}}} g_s(\mathbf{r})\, g_{s'}(\mathbf{r}) \cos(\phi_s - \phi_{s'}). \tag{2.42}$$

The time average equals the incoherent intensity sum over each single spot plus an phase dependent interference term for each frequency order. With $f_s = f_{x,i} + f_{y,j}$ time dependent interference occurs for $k_{x,i} + k_{y,j} = k_{x,i'} + k_{y,j'}$. For a 3×4 grid with equal frequency width, $k_{x,i} = 3i$ and $k_{y,j} = 2j$, exactly one pair of spots has the same frequency. The two diagonally

opposite corner spots, as already shown in Figure 8, cause spatial interference with their contribution to the group field:

$$k_{(0,3)} = k_{(2,0)} = 6, \qquad H_6 = g_{(0,3)} e^{i\phi_{(0,3)}} + g_{(2,0)} e^{i\phi_{(2,0)}}. \tag{2.43}$$

For $N_x = N_y$, all spots along a given anti-diagonal ($i + j = \text{const}$) share the same frequency, contributing to the spatial interference. For a single pair of spots, the static interference term in Equation 2.42 vanishes when their phase difference satisfies $\phi_s - \phi_{s'} = \pm\pi/2$. Calculating the variance of the intensity with $\langle I^2 \rangle_t = \sum_d |D_d|^2$ results in:

$$\text{Var}_t[I(\mathbf{r},t)] = \langle I^2 \rangle_t - \langle I \rangle_t^2 = \sum_d |D_d(\mathbf{r})|^2 - |D_0(\mathbf{r})|^2 = \sum_{d\neq 0} |D_d(\mathbf{r})|^2 = 2\sum_{d>0} |D_d(\mathbf{r})|^2 . \tag{2.44}$$

To characterize the beating, a time-dependent uniformity $U_t(\mathbf{r})$ is defined as the ratio of the temporal standard deviation to the temporal mean intensity at a given position $\mathbf{r}$:

$$U_t(\mathbf{r}) = \frac{\sigma_I(\mathbf{r})}{\langle I(\mathbf{r}) \rangle_t} = \frac{\sqrt{\text{Var}_t[I(\mathbf{r},t)]}}{D_0(\mathbf{r})} = \frac{\sqrt{2\sum_{d>0} |D_d(\mathbf{r})|^2}}{D_0(\mathbf{r})}. \tag{2.45}$$

This quantity captures the temporal variations of the intensity at each position. The mean time dependent uniformity over a region of interest is then given as:

$$U_t = \left\langle U_t(\mathbf{r})^2 \right\rangle_R^{1/2} . \tag{2.46}$$

Squaring the time-dependent uniformity prevents positive and negative fluctuations from cancelling each other out when averaging over the region of interest. The uniformity can be expressed as the quadratic sum of the contributions from the individual spot orders with $\sigma_d^2(\mathbf{r}) = 2|D_d(\mathbf{r})|^2$ as:

$$\left\langle U_t(\mathbf{r})^2 \right\rangle_R^{1/2} = \left\langle \frac{\sigma_I(\mathbf{r})^2}{\langle I(\mathbf{r}) \rangle_t^2} \right\rangle_R^{1/2} = \left(\sum_{d>0} \left\langle \frac{\sigma_d^2(\mathbf{r})}{\langle I(\mathbf{r}) \rangle_t^2} \right\rangle_R \right)^{1/2} \equiv \left(\sum_{d>0} (U_{t_d})^2 \right)^{1/2}. \tag{2.47}$$

With U_t a value is given that can be used to evaluate spatial and temporal fluctuations of a profile. The smaller U_t is the more uniform and temporally stable the profile becomes.

3 Test Setup for generating Top Hat profiles with a Beam Shaper

To generate beam profiles with uniform intensity, the Beam Shaper FBSR-800-3.5 manufactured by the company TOPAG is used. The incoming Gaussian beam requires a specific $1/e^2$ beam diameter depending on the used model. In this case a beam diameter $d = 2\omega = 3.5\,\text{mm}$ is needed [9]. After passing through the Beam Shaper, a focusing lens has to be used to generate the Top Hat profile. The resulting beam diameter d', as specified by the manufacturer, is approximately:

$$d' \approx \frac{2\lambda f}{Md}, \tag{3.1}$$

where λ is the wavelength of the incident laser light, f is the focal length of the focusing lens and M is the magnification of an potential optical setup between the Beam Shaper and the lens, Each setup described in the following uses the Lens Optics Objective with $f_{\text{LO}} = 52.88\,\text{mm}$ instead of a single focusing lens, as well as a glass plate simulating the vacuum chamber window used in the actual experiment. The camera (U3-38J0XLE-M-GL) used to acquire the images has a pixel size of 1.45 µm and is placed behind a microscope objective with a magnification of 43.75. For all calculations in this chapter regarding uniformity and crosstalk, the intensity is uniformly weighted across the entire calculation area. The calculation area for the uniformity is chosen as the 90% intensity level of the respective profile. Additionally, for the crosstalk calculation described in Equation 2.22, the measured beam profile is digitally replicated at the eight positions of a 3×3 structure with a pitch of 5.288 µm, corresponding to the atomic pitch.

3.1 Magnification with a telescope

Prior to evaluating the Beam Shaper for the generation of Top Hat profiles near the resolution limit, the profile produced in the focal plane of the Lens Optics Objective is first measured without any additional magnifying optics. The setup consists of a Beam Expander (Edmund Optics $87 - 564$) behind the Triplet Collimator of the fiber coupler to achieve the necessary beam diameter for the following Beam Shaper. After passing through the Beam Shaper, the laser beam is focused with the Lens Optics Objective and passes the window before being imaged onto the sensor of the camera.
The Beam Expander is set to a magnification of approximately 1.9 in order for the laser beam to reach its necessary diameter for the Beam Shaper. The waist of the Gaussian beam in both the vertical (y) and horizontal (x) dimensions is almost identical with $\omega_x = 1.77(2)\,\text{mm}$ and $\omega_y = 1.76(2)\,\text{mm}$ and both values are within 5% of the desired value.
The resulting Top Hat profile in the focal plane of the Lens Optics Objective has a $1/e^2$ diameter of 22.80(6) µm. The expected beam diameter according to Equation 3.1 is calculated with f_{LO}, resulting in $d' = 24\,\mu\text{m}$. The measured beam profile is approximately 5% smaller than the value specified by the manufacturer, indicating that Equation 3.1 provides only an approximation of the actual beam diameter. The uncertainties in the beam diameters and the subsequent quantities calculated in this chapter arise from fitting an elliptical profile to the measured data.

The Top Hat profile consists of a central peak and a bright outer ring, whose two sides have different intensities. Scanning along the optical axis leads to an increase or decrease in the central peak intensity, while the intensity of the outer ring remains approximately constant. Moving the Beam Shaper perpendicular to the beam path results in a lateral shift of the central peak. The intensity variation along the outer ring could not be corrected by adjusting either the Beam Shaper or the Lens Optics Objective.
By adjusting the position of the camera along the optical axis of the laser beam, different planes along the propagation direction can be observed, with only one camera position corresponding to the focal plane. In addition to the Top Hat profile in the focal plane, a second Top Hat profile with a larger diameter and therefore lower intensity can be observed in another plane. This profile is numerated as a first order Top Hat profile while the one in the focal plane is of zeroth order [24]. Additionally, ellipticity of the beam profile is observed, which may indicate the presence of astigmatism. For the following measurements near the diffraction limit only zeroth order Top Hat profiles are relevant to determine the practical limits of the Beam Shaper in a local Raman Laser setup.
After the Beam Shaper was successfully tested, confirming that the required beam size and profile quality were achieved, a telescope was added to the setup to magnify the beam before it reaches the Lens Optics Objective. This allows a Top Hat profile with a size close to or below the 10 µm limit specified by the manufacturer to be generated in the focal plane [9]. The previews setup is extended using two achromatic lenses with the focal lengths of $f_1 = 45\,\text{mm}$ and $f_2 = 400\,\text{mm}$. The lenses in the setup are separated by a distance equal to the sum of their respective focal lengths. After the telescope, two mirrors, the Lens Optics Objective, the glass window, and the camera are placed. Figure 13 shows the final setup, including an additional Acousto-Optical Deflector (AOD) that is not used when evaluating the effect of the telescope alone. The incoming beam is magnified through the telescope by a factor of $M = f_2/f_1$, resulting in a beam diameter of $d' = {}^{f_2}/_{f_1} \cdot d = 31.1\,\text{mm}$, which is subsequently focused by the Lens Optics Objective. The expected diameter of the Top Hat profile according to 3.1 is $d' = 2.7\,\mu\text{m}$. For the creation of a Top Hat profile in the focal plane it is relevant that the beam diameter is smaller than the optics in the beam path. If the aperture of any optical component is too small compared to the shaped beam diameter, the beam profile is spatially filtered before reaching the Lens Optics Objective. Since the focusing process performs a Fourier transform, this spatial filtering results in a distorted profile.
For this reason two three inch mirrors are placed after the telescope. The limiting optical component in this setup is the tube of the Lens Optics Objective, which has a free aperture of 34 mm. A simulation of a normalized Super-Gaussian Top Hat beam profile is performed to estimate the quality of the beam profile after passing thorough the Lens Optics Objective. The Super-Gaussian has the form

$$I_0(x,y) = \exp\left[-2\left(\frac{r}{w}\right)^{2n}\right], \tag{3.2}$$

where the order $n = 2$ is chosen as an example and a diameter of $d' = 2\omega = 2.7\,\mu\text{m}$ in the atomic plane was assumed according to Equation 3.1. Starting from an ideal Top Hat beam profile in the atomic plane, the beam profile in front of the Lens Optics Objective is calculated using a Fourier transform. The resulting ideal beam profile in the Fourier plane is then truncated by the aperture and transformed back into the spatial domain. The resulting filtered profile therefore represents the best-case scenario, assuming an ideal initial beam profile without distortions or additional optical losses. The results of this simulation are shown in Figure 9. The aperture cutoff in the Fourier plane leaves only the central structure of the Fourier image.




Fig. 9: Simulated aperture cutoff for a Top Hat profile with all profiles normalized to their respective maximum. a) Top Hat profile to be generated in the atomic plane with a $1/e^2$ diameter of 2.7 µm. b) Cross section plot through a). c) Transformed profile in the Fourier plane in front of the Lens Optics Objective, with the aperture cutoff indicated in cyan. d) Cross section plot of the profile in the Fourier plane. e) Back-transformed beam profile after the aperture cutoff, showing the loss of the Top Hat structure. f) Cross section plot of the back-transformed profile.

Consequently, the back-transformed beam profile no longer has the initial Top Hat structure but instead takes on the form of a Gaussian beam with a diameter of approximately 2.56 µm. For a diameter of 4.5 µm, the first secondary maximum is not truncated by the aperture, allowing the back-transformed profile to retain its Top Hat shape. The tube aperture of the Lens Optics Objective, on the other hand, would need a diameter of 60 mm for a Top Hat profile to be created in the focal plane with a diameter of 2.7 µm. The simulation results can be validated by experimental measurements obtained with the test setup. The resulting image shown in Figure 10 more closely resembles an Airy profile, similar to the profiles already observed in [10], and is far from exhibiting a Top Hat structure. Although the measured profile diameter of 3.36(6) µm is close to the expected value of 2.56 µm, the Gaussian beam profile predicted by the simulation is not observed experimentally. The loss of the uniform structure of the beam profile can either be attributed to the manufacturer's specified minimum beam diameter of 10 µm for the Beam Shaper [9] or to the limited tube aperture of the Lens Optics Objective, which acts as a spatial filter, as discussed above. In either case, Top Hat profiles cannot be generated with this combination of lenses and the used Beam Shaper. Therefore it is concluded that the magnification of the telescope has to be smaller to create a larger beam profile in the focal plane. Additionally this Top Hat profile also has to be smaller than the interatomic distance.




Fig. 10: Left: Image of the shaped beam profile with marked intensity levels taken after the Lens Optics Objective and the $45 - 400$ telescope with a $1/e^2$-diameter of approximately 3.36(6) µm. Right: Horizontal and vertical cross section plots of the taken Image with a visible structure of an Airy function.

In the next iteration, the second achromatic lens is replaced with one with a focal length of $f_2 = 300\,\text{mm}$, while the first lens remains unchanged. The resulting beam diameter is therefore calculated to be $d = {}^{300}/_{45} \cdot 3.5\,\text{mm} = 23.3\,\text{mm}$ which should improve the quality of the focused beam because of less spatial filtering. The expected beam diameter according to Equation 3.1 is 3.6 µm. The resulting image of the beam profile is shown in Figure 11. The beam itself exhibits an elliptical profile with $1/e^2$-diameter of 5.20(8) µm and 4.42(6) µm along its principal axes and a tilt angle of $52.8(2)^\circ$ relative to the horizontal axes. These values differ by up to 44% from the expected values and strongly indicate that the size limit specified by the manufacturer has been reached. Within the region enclosed by the 90% intensity level, indicated in cyan, with $d_a = 2.26(4)$ µm and $d_b = 1.92(4)$ µm, the uniformity of the profile is $U = 3.85(11)\%$ and the crosstalk is $\eta = 3.41(115)\%$. Also elliptical side structures resembling the secondary maximum of an Airy profile are visible around the central structure while in the upper right half of the image its intensity increases compared to the remaining parts. The ellipticity of the profile could not be reduced by adjusting the Beam Shaper or the Lens Optics Objective. The telescope itself with its two achromatic lenses was not adjusted and could therefore contribute to the observed deviation in the profile shape due to manual alignment inaccuracies. In particular, the observed ellipticity could potentially be caused by astigmatism introduced by the telescope. However, this effect cannot be investigated with the Beam Shaper, as only the focal plane can be evaluated. Mounting future setups in a tube system could improve the alignment and, consequently, the quality of the magnification. This was not realized in the present test setup due to the different lens diameters and the large distances between the lenses.
Although the generated beam profile has an elliptical shape and larger diameters than specified by the manufacturer, the feasibility of single-site addressing with an AOD is investigated next as a proof of concept.




Fig. 11: a) Image of the shaped beam profile with marked intensity levels, taken after the Lens Optics Objective and the $45 - 300$ telescope. The image is elliptical with approximate diameters of 5.20(8) µm and 4.42(6) µm along both axis. b)+c) Horizontal and vertical cross section plots of the taken elliptic Image.

3.2 Integration of two AODs

To enable single-site addressing with a Top Hat profile, an AOD can be used as already discussed in section 2.3. For addressing the entire two-dimensional atomic plane, two AODs are arranged perpendicular to each other. The center between the two AODs is positioned at a distance equal to the focal length f_1 from the first achromatic lens of the telescope. The beam propagation behind the AOD is depicted in Figure 12. The angle Θ of the deflected light is transformed




Fig. 12: Schematic drawing of the beam propagation behind the AODs using a telescope and the Lens Optics Objective. For simplification just one AOD is drawn. The angle Θ of the deflected light is transformed into a lateral shift by the first lens f_1 and imaged onto the camera sensor by the second achromatic lens f_2 and the Lens Optics Objective.

into a lateral shift by the first lens f_1. Afterwards this shift is imaged onto the camera sensor by the second achromatic lens f_2 and the Lens Optics Objective. The resulting position r on the camera sensor depends on the angle of deflection Θ and can be calculated by geometric considerations with:

$$r = \frac{f_1}{f_2} f_{\mathrm{LO}} \tan\Theta. \tag{3.3}$$

The maximum angle of deflection for the used AOD is $\Theta_{\mathrm{max}} = \pm 21.5\,\mathrm{mrad}$ [21]. Using Θ_{max} and the current combination of the achromatic lenses $f_1 = 45\,\mathrm{mm}$ and $f_2 = 300\,\mathrm{mm}$ in Equation 3.3 results in a total addressable region of 341.3 µm × 341.3 µm which correspondents to a 64×64 grid of atoms with a pitch of 5.288 µm. The beam waist in the atomic plane can be calculated by:

$$\omega = \frac{f_1}{f_2} \frac{\lambda f_{\mathrm{LO}}}{\pi \omega_{\mathrm{in}}}. \tag{3.4}$$

This equation does not take the effect of the Beam Shaper into account. Using the beam diameter instead gives:

$$d' = \frac{2}{\pi} \frac{2\lambda f_{\mathrm{LO}}}{d(f_2/f_1)}. \tag{3.5}$$

Together with the magnification of the telescope, Equation 3.1 is therefore multiplied by the factor $2/\pi$. Consequently, the corresponding Top Hat profile is approximately 1.5 times larger than the corresponding Gaussian beam profile.
A schematic of the adjusted setup with an AOD is shown in Figure 13. For the first test, the driving frequency was set to the central frequency of 102.5 MHz for both the horizontal and vertical beam deflection directions, as specified in data sheet [21]. At this frequency, the diffracted laser beam experiences no net deflection, since the two AOD crystals are cut to compensate for each other's angular refraction. The resulting image taken with the camera is shown in Figure 14. In the center of the profile, a flat region resembling the previously observed Top Hat structure is visible. Additionally, two local intensity maxima can be observed within the central region. These maxima are positioned symmetrically around the center and are not visible in the corresponding cross section plots due to their diagonal positioning. Adjusting the Beam Shaper results in the same behavior as observed previously, as moving the Beam Shaper perpendicular to the beam path causes a lateral shift of the central intensity structure. The profile still exhibits an elliptical structure with a tilt angle of $1.9(11)°$ relative to the horizontal axes. The $1/e^2$ diameters along the principal axes are 6.4(2) µm and 5.64(18) µm, respectively, representing an increase compared to the profile measured without the AOD. This could be




Fig. 13: Schematic setup of the beam shaper to generate a Top Hat profile in the focus of a Lens Optics Objective after the deflection with an AOD and the magnification with a $45 - 300$ telescope.




Fig. 14: a) Image of the shaped beam profile deflected with an AOD taken after the Lens Optics Objective and the $45 - 300$ telescope. Three different intensity levels are marked. b)+c) Horizontal and vertical cross section plots of the taken elliptic Image.

caused by truncation at the aperture of the AOD housing, resulting in a smaller beam size in front of the telescope that is subsequently focused into the atomic plane with a larger waist. The active aperture of the AOD is 7 mm [21]. Thus, a beam with a $1/e^2$ diameter of $d = 3.5$ mm should not be truncated by the aperture. Nevertheless, a cutoff at the housing is visible when observing the beam with an infrared viewer. The elliptical structure of the beam is now dominated by a distortion along the diagonal axis. Hereby the upper right half of the beam shows a large side structure spanning over several micrometers while the opposite edge shows no such behavior. These distortions are suspected to originate from spatially dependent phase variations introduced by the AOD crystal. As the acoustic wave propagates through the crystal, different parts of the extended Gaussian beam interact with the acoustic wave at different times, potentially introducing a spatially varying phase. Furthermore, the crystal geometry may result in different optical path lengths across the beam, introducing additional phase variations. The resulting beam profile could not be reproduced reliably, even when different optical components were used. Previous attempts to integrate this AOD into the movable tweezer have already proven difficult due to persistent side structures that could not be eliminated through optical adjustments.
Within the region enclosed by the 90% intensity level, indicated in cyan, with $d_a = 2.30(12)$ µm and $d_b = 2.02(12)$ µm, the uniformity of the profile is $U = 4.82(30)\%$ and the crosstalk is $\eta = 8.72(191)\%$. While the uniformity has increased by 25%, the crosstalk has increased by approximately a factor of three compared to the profile without the AOD, due to the dominant distortions.

A proof of concept for generating Top Hat-like profiles with a Beam Shaper at a beam size of approximately 5 µm has been demonstrated, thereby surpassing the manufacturer's specified limit of 10 µm [9]. The size of the resulting profiles are already close to the atomic pitch of 5.288 µm, with a crosstalk of approximately 3 %. Further reducing the beam size and its

resulting crosstalk is prevented by the aperture cutoff at the tube of the Lens Optics Objective. The quality of the beam profile deteriorates after passing through the telescope, as the profile takes on an elliptical shape. After passing through an AOD, the characteristic Top Hat structure can still be observed, while additional distortions further increase the uniformity and the crosstalk of the beam profile. The observed distortions are suspected to originate from the AOD itself, resulting in a beam profile that could not be reproduced reliably, even when different optical components are used.
Accordingly, this approach is rejected, as the resulting intensity profile is unsuitable for single-site addressing of ^{85}Rb atoms. In particular, the crosstalk of approximately $9\,\%$ would significantly compromise the fidelity of single-qubit gate operations.

4 Multi-tone Simulation for a Top Hat profile

The second approach for generating uniform intensity profiles uses two perpendicular multi-tone Acousto-Optical Deflectors (AODs) to superimpose multiple deflected laser beams. In the resulting Cartesian coordinate system, each AOD defines one spatial dimension, with the intensity profiles therefore being rectangular and for the same frequency width in both dimensions square shaped. Before constructing a new setup with a suitable pair of achromatic lenses with focal lengths f_1 and f_2, as illustrated in Figure 12, theoretical simulations are performed using a Python-based repository [25]. These simulations aim to determine the optimal parameters for generating a uniform intensity profile using two perpendicular multi-tone AODs. The parameters that have to be optimized are:

- The focal lengths of achromatic lenses f_1 and f_2
- The number of tones N_x and N_y in both dimensions of the atomic plane
- The beam waist ω_{in} in front of the achromatic lens f_1, which is then imaged into the atomic plane as ω according to Equation 3.4
- The frequency width of the tones in the AOD, effectively determining the profile width W in the atomic plane according to Equation 3.3
- The amplitudes of each tone $A_{x/y} = \{r_1, r_2, .., r_{N_{x/y}}\}$

Instead of using a Gaussian beam profile as the basis of the multi-tone simulation, an Airy profile is used to evaluate the optical properties of the generated beam profile near the diffraction limit. A first limitation of the free variables is done to limit the number of parameters that have to be optimized. The lenses must be selected to ensure that the entire atomic grid of more than 40×40 atoms can be addressed, as specified by Equation 3.3. Furthermore, for a new optical setup a long focal length f_2 is needed for the second achromatic lens due to a long optical path between the Lens Optics Objective and f_2 in the actual experiment. Longer focal lengths are also preferable because they can reduce spherical aberration. The two achromatic lenses are chosen accordingly as $f_1 = 75\,\text{mm}$ and $f_2 = 750\,\text{mm}$ so a scanning range of $r_{\text{max}} = 227.5\,\mu\text{m}$ or an addressable atomic grid of 43×43 atoms can be generated according to Equation 3.3. Based on Equation 3.3, the conversion factor between the frequency width W of the AOD and the actual width of the profile is $c = 6.316\,\mu\text{m/MHz}$ for this combination of lenses. The beam waist in the atomic plane is in the order of $\approx 1\,\mu\text{m}$, depending on the beam waist in front of the AOD, as given by Equation 3.4. The number of tones for the profile is chosen to be $N_x = 3$ and $N_y = 4$. A optimized set of $N_x = 2$ and $N_y = 3$ tones has an overlap for the spots on its anti-diagonal axis, violating Equation 2.26, resulting in spatial interference and is therefore not suitable for the implementation of a Top Hat profile. Although uniform profiles with $N_x = 4$ and $N_y = 5$ and higher numbers of tones can in principle be generated, they require a larger profile width than the 3×4 configuration, resulting in a larger profile and consequently an increased crosstalk. Additionally the intensity amplitudes of these tones are assumed to be symmetrical around the center and are defined by the ratio of the two outer tones to the inner ones. With this parametrization, the amplitudes for the tones are given by $A_x = [r_x, 1, r_x]$

and $A_y = [r_y, 1, 1, r_y]$. With these limitations, simulations can be conducted to find suitable parameters for the generation of multi-tone Top Hat profiles that minimize the uniformity U and the crosstalk η. The list of free parameters to be optimized by the simulation is:

- The beam waist ω_{in} in front of the achromatic lens f_1 which is then projected into the atomic plane as ω
- The frequency width of the tones in the AOD, effectively determining the width W of the profile in the atomic plane
- The amplitude ratio of the outer tones to the inner ones in both dimensions r_x and r_y

Since the generated beam profiles have a square structure, the region of interest used to calculate the uniformity and crosstalk is square as well. For the uniformity the region of interest is limited by the profile width W. Larger regions than W would worsen the uniformity for including the falling edge of the profile and are therefore excluded. The region of interest for the crosstalk is limited by a square with the length equal to the pitch of the atomic grid spacing of 5.288 µm. A visualization of these areas is shown in Figure 21.

4.1 Simulation with an uniform distribution

The fixed areas of pitch and tone array are first used as the calculation area within the simulation, which is called hard metric for further comparison. These calculation areas are chosen on this scale to ensure that the optimized intensity profiles uniformly illuminate the atoms even in the presence of relative displacements between the dipole trap array and the beam profile. With this approach, an upper estimate for the crosstalk and the uniformity is provided.
A uniform distribution is used for the calculation area and the values are summed over the corresponding range containing N_h data points:

$$\langle I \rangle_h = \frac{1}{N_h} \sum_{i=1}^{N_h} I_i \quad \Delta I_h = \sqrt{\frac{\sum_{i=1}^{N_h} (I_i - \langle I \rangle_h)^2}{N_h}}. \tag{4.1}$$

To find a proper set of parameters, an optimization variable J_h is introduced which is a weighted sum of uniformity and crosstalk with weight $\alpha = 0.7$:

$$J_h = \alpha U_h + (1 - \alpha)\eta_h. \tag{4.2}$$

$\alpha = 0.7$ is chosen as a compromise, balancing the importance of uniformity and crosstalk, as $\alpha = 0.9$ underestimates the contribution of crosstalk, whereas $\alpha = 0.5$ assigns it too much weight. For a given set of spot waist and profile width, the amplitude ratios r_x and r_y are optimized to minimize J_h. The waists upper bound is determined by the aperture of the Lens Optics Objective with 1.7 mm and a magnification of $M = 10$, introduced by the telescope while as a lower bound of 0.8 mm is chosen due to the diffraction limit. The range for the spot waist in the atomic plane is therefore approximately 0.8 µm − 1.7 µm. The range for the frequency width at the AOD is chosen to be 0.25 MHz − 0.45 MHz, which translates to a profile width of 1.58 µm − 2.84 µm. The result of the optimization for J_h is shown in Figure 15. For the overlap of the corner spots according to Equation 2.26, the corresponding area is excluded from further calculations and left blank due to the expected interference. The crosstalk η_h increases with a rising waist of a single spot while remaining approximately constant across the profile




Fig. 15: Left: Two-dimensional plot of the combined score J_h over the spot waist and the profile width with a linear fit for the minimum path. Right: Crosstalk η_h plotted for the same variables. For a larger spot waist the crosstalk increases.

width. η_h lies in a range of $5\,\%$ to $22\,\%$ and shows no additional side structures. J_h exhibits a minimum region around $5\,\%$, which appears to lie along a straight line for $0.8\,\mu\text{m} - 1.3\,\mu\text{m}$ and $1.8\,\mu\text{m} - 2.8\,\mu\text{m}$. In this region, a linear function can be fitted to the data:

$$W(\omega) = a \cdot \omega + b = 2.25(5) \cdot \omega + 0.060(5)\,\mu\text{m}. \tag{4.3}$$

Along this linear fit, J_h lies between $4.1\,\%$ and $5.3\,\%$. This linear relationship between profile width and spot waist indicates that wider beam profiles require larger individual spots to maintain a low uniformity. An ideal model following this description would have a zero constant term. A potential working point is can be found for $W = 2.34\,\mu\text{m}(0.37\,\text{MHz})$, with an corresponding waist of $\omega = 1.01\,\mu\text{m}$ and the amplitude ratios $r_x = 0.97 \quad r_y = 1.13$. The uniformity of this configuration is $U_h = 3.47(4)\,\%$ and the crosstalk is $\eta_h = 8.17(2)\,\%$. The crosstalk, defined for the eight nearest neighboring profiles, represents an upper bound. The crosstalk decreases with fewer neighboring profiles, with each individual profile contributing approximately $1\,\% - 2\,\%$ to η_h. A major flaw of using a uniform distribution is that it does not take the actual position of the atom into account. In this model, the probability to find the atom in the upper right edge of the area is the same as in its center. Using large calculation areas relative to the size of a single spot in the hard metric prevents to resolve the crosstalk contributions from the side structures of neighboring Airy profiles. The use of the pitch square always includes multiple secondary maxima and minima within the crosstalk at once, revealing no information for a specific set of desirable parameters to actually reduce the crosstalk for each individual atom. To integrate a spatially resolved crosstalk into the simulation, another approach for the simulation is used.

4.2 Atom-weighted simulation

To take the actual atom position into account, the spatial probability density $|\Psi|^2$ is used to calculate the crosstalk and the uniformity:

$$\langle I \rangle_w = \sum_i I_i \cdot |\Psi|^2 \quad \Delta I_w = \sqrt{\sum_i (I_i - \langle I \rangle_w)^2 \cdot |\Psi|^2}. \tag{4.4}$$

The spatial probability density is parametrized with the atom temperature $T = 17(2)$ µK and a radial trap frequency of $\nu_r = 60.4(24)$ kHz [3]. With these parameters, the σ-width is given as $\sigma = 108(8)$ nm and $|\Psi|^2$ can be parametrized according to Equation 2.16.
The Airy profiles used for the individual spots exhibit secondary maxima and minima that can influence the calculated crosstalk but are not resolved using the hard metric. Restricting the effective calculation area, according to the spatial probability density of the atoms, allows side structures to be resolved more accurately, thereby better minimizing the crosstalk of the generated beam profile visible to the atom.
A simulation using [25] is conducted with this atom-weighted calculation metric. With the same parameter range for the profile width and the spot waist, an optimization is performed for the weighted sum with $\alpha = 0.7$:

$$J_w = \alpha U_w + (1 - \alpha)\eta_w, \tag{4.5}$$

The results are shown in Figure 16. For the overlap of the corner spots, according to Equation 2.26, the corresponding area is left blank due to the expected interference. J_w lies between $0.5\,\%$ to $3.3\,\%$. No linear fit can be found for its minimum, since several minimum regions for J_w form vertical stripes across the profile width W. These stripes result from the crosstalk η_w and are caused by secondary maxima of the Airy profiles. Increasing the waist of the single Airy spots shifts the positions of the secondary maxima and minima of each spot in the same direction relative to the center. This results in a stripe-shaped minimum region for the crosstalk η_w, as the secondary intensity minima of numerous spots in neighboring profiles coincide with the atomic position in the center. The first stripe is caused by the minima of vertically and horizontally neighboring profile spots with $\omega \approx 0.85$ µm.The second stripe is caused by the




Fig. 16: Left: Two-dimensional plot of the combined score J_w over the spot waist and the profile width. No linear fit can be found for J_w. Right: Crosstalk η_w plotted for the same variables. Vertical stripes for the local minima of η_w are visible.

minima of diagonally neighboring profile spots with $\omega \approx 1.1\,\mu m$. Along one stripe the crosstalk stays almost constant. Increasing the profile width moves the closest spots of neighboring beam profiles closer to the central profile and the atom while increasing the distance for the outer ones, resulting in a net change of zero for the crosstalk. For larger spot waists, no stripes are visible. The crosstalk the atom experiences depends mostly on the waist of the central structure of the Airy profile, since it determines the pattern of local minima and maxima visible to the atom. η_w depicts discontinuities up to $5\,\%$ for large profile widths.
This approach if found to fulfill its purpose of resolving the crosstalk η_w caused by side structures of the Airy profiles, in contrast to the hard metric. The working point identified for the hard metric at a profile width of $W = 2.34\,\mu m$ is also promising when evaluated using the atom-weighted metric. The corresponding waist is $\omega = 1.05\,\mu m$, with amplitude ratios of $r_x = 1.004$ and $r_y = 0.945$. For these parameters, the atom-weighted uniformity is $U_w = 0.27(3)\,\%$, and the crosstalk is $\eta_w = 1.35(5)\,\%$. The optimization for each parameter set yields cases in which the crosstalk and atom-weighted uniformity are minimized for amplitude ratios close to the imposed optimization limits ($r_{x,y} \in [0.1, 10]$). Those amplitude ratios are no longer a realization of a 3×4 profile but rather one of for example 2×2 spots, violating a basic assumption of the simulation.
An example for such a local minimum is the case $r_x = 2 \quad r_y = 0.18$ with a waist of $\omega = 1.11\,\mu m$ and a width of $W = 2.46\,\mu m$. The uniformity in this case is $U_w = 0.91(1)\,\%$ and the crosstalk is $\eta_w = 2.40(3)\,\%$. At the same time, the uniformity calculated with the hard metric with $U_h > 33\,\%$ reveals a beam profile far from a Top Hat that only shows a uniform intensity in the central region visible to the atom. The resulting beam profile in this case is shown in Figure 17. The power density at the atom's location can vary significantly depending on the positioning of multi-tone beam profile and dipole trap relative to each other. Thus, such a case loses the advantage of a uniform beam profile.
The observed discontinuities in the plot of η_w in Figure 16 are found to reveal more such unpractical optimization results in which the optimized amplitudes reach the optimization limits.




Fig. 17: (a) Horizontal cross section plot of the uneven beam profile showing a uniform area for the atom at the minimum between the outer spots. (b) Vertical cross section plot of the uneven beam profile revealing a small even region visible to the atom. (c) Two-dimensional plot of the beam profile from the weighted optimization simulation. No Top Hat-like structure is visible

4.3 Combination of both simulations

The first approach using hard metric to find parameters for large, uniform intensity profiles does not resolve the crosstalk contributions of secondary maxima of neighboring Airy profiles. The atom-weighted approach provides this missing information but can favor solutions that do not preserve the desired large, uniform intensity profile. To account for both requirements, the two approaches are combined to identify a set of parameters that balances the profiles uniformity and crosstalk on both scales.
The uniformity and the crosstalk have a different order of magnitude for the tow calculation metrics, as previously determined for the potential working point. Therefore the mean value is not a good way of combining them. The combined crosstalk η_c and uniformity U_c, minimized during the optimization of the four parameters, consist of the respective mean values of the previous two metrics and an additional penalty term defined as the absolute difference between both cases with a weighting factor of $\chi = 0.75$:

$$U_c = \frac{1}{2}(U_w + U_h) + \chi|U_w - U_h| \tag{4.6}$$

$$\eta_c = \frac{1}{2}(\eta_w + \eta_h) + \chi|\eta_w - \eta_h| \tag{4.7}$$

The weighting factor $\chi = 0.75$ is chosen to ensure that the penalty term is weighted more strongly than the mean while preventing it from dominating the overall metric. This ensures that when the two metrics evolve in opposite directions, with one improving while the other deteriorates, the combined metric still increases if the deterioration outweighs the improvement. The value J_c for the optimization is given by a weighted sum with $\alpha = 0.7$:

$$J_c = \alpha U_c + (1 - \alpha)\eta_c. \tag{4.8}$$

For each pair of profile width and spot waist the amplitudes are optimized to minimize J_c. The results of the optimization is shown in Figure 18. Based on Equation 2.26, the region in which the diagonal spots overlap is left blank for J_c and excluded from further evaluation. Following




Fig. 18: Left: Plot of the combined score J_c over spot waist and profile width with a linear fit along its minimum path and the blank overlap region. Right: Cross section plot of J_c along the linear fit.

the results of this optimized, a linear function can be fitted to the minimum path of J_c for ω and W:

$$W(\omega) = a \cdot \omega + b = 1.98(3) \cdot \omega + 0.27(3)\,\mu\text{m}. \tag{4.9}$$

Compared to the hard metrics, the slope of the linear fit decreases by $12\,\%$, while the constant term increases by more than a factor of four. Along the optimum path itself J_c lies between $4.5\,\%$ and $7.5\,\%$. The shape of the curve for J_c shows a zigzag pattern. This pattern may arise from the finite simulation resolution, as the linear fit is evaluated along discrete values, leading to jumps between neighboring points.
An overview of the optimized uniformities U_h and U_w, crosstalks η_h and η_w and their cross section plots along the linear fit of J_c is shown in Figure 19. For both calculation metrics, the uniformity increases with a larger profile width at a fixed spot waist. This is attributed to the larger spacing between individual spots, which leads to local intensity minima within the central region visible to the atom. A reduced profile width at a fixed spot waist creates profiles with a Gaussian shape. The shape of both the weighted uniformity U_w and the hard uniformity U_h show a minimum bath alongside the linear fit of J_c given by Equation 4.9, as drawn in the




Fig. 19: (a+b) Two dimensional plots of the uniformities U_h and U_w with the linear fit of J_c. Both plots show a minimum path following the linear fit. (c) Cut of U_h and U_w along the linear fit. U_h is approximately constant while U_w decreases. (d+e) Two dimensional plots of the crosstalks η_h and η_w with the linear fit of J_c. (f) Cut of η_h and η_w along the linear fit. η_w depicts a stripe structure while η_h increases with a rising waist.

plot. This linear relationship between profile width and spot waist confirms for the combined approach that wider beam profiles require larger individual spots to maintain low uniformity. A second linear shape for the minimum of the weighted uniformity U_w can be found near the blank overlap region. No linear fit is conducted for this region, since these data points are excluded from the evaluation. Along the linear fit, the hard uniformity remains approximately constant with $U_h = 3.6\,\%$ but depicts a zigzag pattern. The weighted uniformity U_w decreases monotonically without exhibiting a zigzag structure. The minimum of U_w is reached at the maximum profile width of $W = 2.84\,\mu\text{m}$. The resulting profile, consisting of relatively large individual spots, exhibits only small intensity variations across the region visible to the atoms, thereby minimizing U_w. The uniformity alone is not sufficient to identify a suitable set of parameters for the creation of a multi-tone profile, as the crosstalk must also be considered. The hard crosstalk η_h for the combined calculation metric depicts the same structure as for the use of just the hard calculation metric. With a rising spot waist, η_h increases and lies between $6\,\%$ and $21\,\%$. The weighted crosstalk η_w lies between $1\,\%$ and $9\,\%$ and shows a stripe-shaped structure for local minima that arise from the secondary maxima and minima of the Airy profiles. The first stripe is caused by the minima of vertically and horizontally neighboring profile spots, while the second stripe along the waist is caused by the diagonally neighboring profile spots. For higher order minima, their overlap increases and starts to simultaneously reach the center, causing the stripe to flatten out and bend. The observed discontinuities in Figure 16 do not occur for η_w calculated with the combined metric. The absence of discontinuities confirms the necessity of the combined calculation metric to generate large, uniform beam profiles that can resolve the crosstalk visible to the atom caused by secondary maxima of the Airy spots. The difference in the effective calculation area of the two crosstalk metrics results in a absolute difference between the two crosstalks. Along the linear fit η_h increases monotonically, showing small bends at the position of local maxima and minima of η_w. The local extrema of the Airy spots, visible for η_w, cannot be resolved due to the large area over which η_h is calculated. Beside from this oscillating pattern, η_w increases along the cross section of the linear fit of J_c. An overview of the optimized amplitude ratios r_x and r_y, together with their cross section plots along the linear fit of J_c, is shown in Figure 20. Both amplitude ratios increase up to $r_{xy} = 4$




Fig. 20: (a+b) Two dimensional plots of the amplitude ratios r_x and r_y with the linear fit of J_c. Around the region of the linear fit, both amplitude ratios are approximately one. (c) Cut of r_x and r_y along the linear fit. r_x remains approximately constant and r_y shows a slight linear increase.

near the excluded evaluation area, indicating this regions belongs to a uniform 2×2 multi-tone

profile or other configurations. Apart from this limit, both amplitude ratios remain close to 1.0 across the entire range of spot waists and profile widths, with $r_y > r_x$. Along the linear fit of J_c, r_y increases from 1.13 to 1.19, exhibiting the previously observed zigzag pattern, while r_x remains nearly constant at $r_x = 0.97$.
A suitable working point is again found for $W = 2.34\,\mu\text{m}$ with a corresponding waist of 1.04 µm according to the linear fit, which translates to $\omega_{in} = 1.29\,\text{mm}$ in front of the AOD. The amplitude ratios are $r_x = 0.97$ and $r_y = 1.16$. With the hard metrics, the uniformity is $U_h = 3.56(3)\,\%$ and the crosstalk is $\eta_h = 8.40(5)\,\%$. In the weighted case, the uniformity is $U_w = 0.43(5)\,\%$ with a crosstalk of $\eta_w = 1.40(3)\,\%$. The uncertainties are resulting from the linear fit $W(\omega)$. Compared to the discussed working point for the hard and the atom-weighted metrics, the crosstalk and uniformity have slightly increased ($\sim 0.2\,\%$) within the margin of the uncertainty in both cases. A visualization of the resulting multi-tone Top Hat profile for these parameters is shown in Figure 21. The horizontal cross section of the beam profile exhibits an almost flat intensity profile up to the edge of the uniformity region, while the vertical cross section reveals a small dip in the central intensity. In both cases, the spatial probability density is much smaller than the beam profile and its substructure, resulting in the optimized low uniformity η_w. A cross section plot of the central region for the light from the eight neighboring




Fig. 21: (a+b) Horizontal and vertical cross section plots of the optimized Top Hat beam profile for the chosen working point showing a uniform area for the atom in the center. (c) Two-dimensional plot of the optimized Top Hat beam profile and the regions of evaluation. (d+e) Horizontal and vertical cross section plots of the light of neighboring profiles illuminating the center. (f) Two-dimensional plot for eight neighbors of the optimized Top Hat beam profile with the regions of evaluation.

beam profiles illuminating the center is shown in Figure 21 (a+b). The intensity, responsible

for the crosstalk, is normalized to the maximum intensity of the central beam profile. In the center, the neighboring light has a global minimum of approximately $1.5\,\%$ for both directions. Going outwards, the intensity increases up to $5\,\%$ at the edges of the crosstalk region. In both cases, the intensity depicts a series of local minima and maxima. For the horizontal direction, shown in (a), the ratio of maximum and minimum is more pronounced. Beyond the crosstalk region, the rising intensity indicates the neighboring beam profile.
Using 4×5 tones instead would result in a much wider profile width needed for a uniform profile with a fixed waist of $\omega = 1\,\mu\text{m}$, increasing the atom-weighted crosstalk. For $\omega = 1\,\mu\text{m}$ and a profile width of $W = 3.16\,\mu\text{m}$, the atom-weighted crosstalk would be $\eta_w = 3.0\,\%$ significantly distorting single-qubit gate operations compared to the working point of the 3×4 profile. Instead, the spot waist has to be reduced to $0.65\,\mu\text{m}$ at a constant profile width of $W = 2.34\,\mu\text{m}$ to generate a uniform beam profile with comparable values for the uniformity and the crosstalk. Such a small spot waist requires an incoming beam waist of $\omega_{\text{in}} = 2.06\,\text{mm}$ in front of the AOD, which would be subject to truncation. After the telescope, the magnified beam would experience an additional cutoff at the aperture of the tube of the Lens Optics Objective, making this spot waist impractical for the intended setup.

4.3.1 Beam Pointing relative to the Dipole Trap

If the dipole trap, and thus the atom, is displaced from the center of the beam profile, for example due to beam-pointing errors caused by long optical paths of the used laser systems, the local intensity and the crosstalk of the atom can differ from their values at the center. This can lead to variations in the excitation probability and reduce the fidelity of the performed gate operations. The main advantage of a Top Hat profile is its low uniformity, which allows for small relative displacements between the dipole and the center of the Top Hat beam profile without significantly compromising the fidelity of gate operations.
To evaluate the advantage for the optimized multi-tone profile, the atom's position relative to the Top Hat profile is varied, and the resulting changes in the uniformity and the crosstalk are calculated. Only the atom-weighted case is evaluated, since shifts of the uniformity and the crosstalk for the hard metric are mainly geometrical. The atom is shifted outward from the center up to the outermost tone in the horizontal, vertical and diagonal direction.
The resulting change in uniformity and crosstalk is shown in Figure 22. The uniformity stays close to $1\,\%$ over the inner two thirds of the array for all three directions. When the atom reaches the outermost tone, the falling edges of the profile are included in the calculation and U_w rises to $3.8\,\%$ horizontally and $6.9\,\%$ vertically. The two axes differ because the profile consists of different numbers of tones per axis. The 3×4 grid has equal spacing in both directions but is positioned such that the horizontal axis through its center runs between the spots rather than through them. This means the atom is moved horizontally within an intensity valley while passing through the spot centers vertically. Additionally, the amplitudes differ for r_x and r_y which also causes differences in the uniformity. Along the diagonal axis the curve stays lowest with $2.2\,\%$ and reaches a local minimum with $0.81\,\%$ at $r = 0.94\,\mu\text{m}$. At the corner of the profile with $r = 1.65\,\mu\text{m}$ the uniformity is highest with $9.0\,\%$, since two falling edges are included in the calculation of the standard deviation. In all cases the uniformity stays below $5\,\%$ for displacements up to $1\,\mu\text{m}$ from the center. For the expected maximum displacement from the profile center, corresponding to the 3σ width of $3\sigma \approx 0.3\,\mu\text{m}$, the uniformity can be considered stable.
The crosstalk increases in all three directions and reaches a maximum of $3.25\,\%$ at $r = 0.7\,\mu\text{m}$ horizontally, $2.38\,\%$ at $0.85\,\mu\text{m}$ vertically and $3.51\,\%$ at $0.94\,\mu\text{m}$ diagonally. The maximum of

η_w is caused by the secondary maxima of the neighboring profiles. Once the atom is shifted further the crosstalk decreases up to the edge of the beam profile.




Fig. 22: Calculated uniformity U_w and crosstalk η_w for the atom displaced from the site center along the horizontal, the vertical and the diagonal to the outermost tone

4.4 Comparison with a single spot

Another method for the single-site addressing of ^{85}Rb is the use of a single Airy profile. This has the advantage of leaving just the initial beam waist as one parameter for the optimization while eliminating interference concerns. The waist as the only free parameter for Airy profiles is optimized in a simulation [25]. The hard and the atom-weighted calculation metric are used to give an estimation of a good set of potential waists. The calculation area of the hard metric along the tone square has to be replaced with a constant area due to the use of just one tone per profile. The area chosen for this is a circle with radius 1 µm. Since the tube of the Lens Optics Objective has a diameter of $d = 34$ mm, the maximum of the initial waist is set to $\omega_i = 1.7$ mm which translates to 0.8 µm within the atomic plane. The maximum value for the waist within the atomic plane is limited by the pitch of the atomic grid and is therefore set to 2.5 µm, which translates back to an initial waist of $\omega_i = 0.54$ mm. For a better comparison, two hard metrics are used for the crosstalk. The first uniformity η_h uses the same definition as before with a pitch sized square, while the second one $\eta_{h,\mathrm{circ}}$ uses the area of the circle with radius 1 µm like the uniformity. The uniformity and the crosstalk of the hard calculation metrics for different waists of a single Airy profile are shown in Figure 23. The uniformity U_h decreases with an increasing waist ω, as the falling edges of the broader beam profile are starting to lie outside the calculation area. Consequently, the standard deviation decreases, resulting in a lower uniformity. On the other hand, the crosstalk increases in both cases with a rising waist, since neighboring secondary maxima extend into the calculation area. The pitch square crosstalk η_h is more than three times larger than the circular crosstalk $\eta_{h,\mathrm{circ}}$ due to the greater area of included neighboring light. The smaller the calculation area, the better the side structures of the Airy profiles can be resolved. Both curves show a plateau from 1.75 µm to 2 µm where the uniformity has already decreased below 20 %. The crosstalk $\eta_{h,\mathrm{circ}}$ exhibits a local minimum at a waist of approximately $\omega = 1.9$ µm. After the plateau both crosstalks




Fig. 23: Plot of the uniformity U_h and the crosstalk η_h calculated with the hard metric shown for different waists of a single Airy profile. For the crosstalk the two definitions with the pitch square and the circle with radius 1 µm are used.

increase, reaching up to $\eta_h = 14\,\%$ and $\eta_{h,\mathrm{circ}} = 7\,\%$. A suitable working point can be found for $\omega = 1.9\,\mu\mathrm{m}$. With the hard metrics, the uniformity is $U_h = 13.9(1)\,\%$ and the crosstalk for both calculation areas is $\eta_h = 12.5(1)\,\%$ and $\eta_{h,\mathrm{circ}} = 1.62(2)\,\%$.
The uniformity and the crosstalk weighted with the spatial probability density of the atom are shown in Figure 24. The uniformity U_w decreases with an increasing waist within the




Fig. 24: Uniformity U_w and crosstalk η_w weighted with the spatial probability density of the atom shown for different waists of a single Airy profile. For $\omega = 1.9\,\mu\mathrm{m}$ the parameters reach a suitable working point for experimental use.

atomic plane and stays almost completely below $5\,\%$ starting from $6.7\,\%$. The crosstalk shows

an oscillating pattern already observed for the multi-tone approach in Figure 19, resulting from the minima and maxima of the neighboring Airy profiles. For the whole scanned range of the waist within the atomic plane, the crosstalk stays below $8\,\%$. Furthermore, a crosstalk η_w larger than $2.5\,\%$ is only reached for waists above 2.1 µm. The working point $\omega = 1.9\,\mu\text{m}$, selected based on the hard metrics, also provides suitable values for the weighted case, with a uniformity of $U_w = 1.06(15)\,\%$ and a crosstalk of $\eta_w = 0.15(4)\,\%$, with it being minimized due to the side structures of neighboring Airy profiles. The other local minima of the crosstalk are discarded as potential working points due to their higher uniformities. Therefore, the last minimum in the specified range is selected as this waist exhibits the lowest uniformity.
A visualization of the Airy profile for the chosen working point is shown in Figure 25. With this choice for the waist, the secondary maxima of the Airy profile lie outside the calculation area of the crosstalk (red) and therefore contribute light to its neighbors, increasing the hard crosstalk η_h. The atom in the profile center receives almost no light from neighboring profiles since the global intensity minimum coincides with the maximum of the spatial probability density.




Fig. 25: The calculation area of the uniformity in the plot is given by a circle with radius 1 µm. For the crosstalk the shown calculation area is the pitch square. (a) Cross section of an Airy profile with $\omega = 1.9\,\mu\text{m}$ together with the used areas for the calculation of uniformity and crosstalk. (b) Two-dimensional plot of one Airy profile with the used evaluation areas. (c) Cross section plot for light of eight neighboring profiles illuminating the central region. (d) Two-dimensional visualization of the eight neighboring Airy profiles responsible for the crosstalk.

4.4.1 Beam Pointing relative to the Dipole Trap

A major disadvantage of Airy spots is the non-uniform intensity distribution along the flanks of the central maximum. Consequently, even small displacements of the dipole trap and thus the atom relative to the center of the Airy profile can alter the local intensity illuminating the atom. This can reduce the fidelity of the performed gate operations. A displacement can be considered in the simulation of a single Airy spot by moving the atom within the profile and calculating the uniformity and the crosstalk alongside it, as previously done for the multi-tone profile. Only the atom-weighted case is considered, since changes in the uniformity and the crosstalk regarding the atom position are of interest.
For an Airy profile on a Cartesian grid, vertical, horizontal and diagonal displacements are identical due to the rotational symmetry of the profile. Therefore, only one displacement direction is considered. Along the diagonal of the spot grid, the change in the crosstalk differs slightly at larger waists due to the Cartesian gird of the spots. The resulting change for the crosstalk is in the same order of magnitude and is therefore not considered further. To evaluate vertical and horizontal atomic displacements, simulations are performed for several waists of the Airy-profile, resulting in two-dimensional maps of the uniformity U_w and the crosstalk η_w as functions of the displacement r and the spot waist ω. The waist is varied from 0.75 µm to 2.5 µm, while the atom is displaced outwards by up to 2.5 µm from the center. In Figure 26 the results of the simulation are shown. For displacements smaller than the waist, the uniformity U_w increases monotonically for all waist values, reaching values up to $U_w = 10\,\%$. For displacements larger than the waist, two lines of local maxima and one line of local minima are visible. These lines are caused by the secondary maxima and minima of the Airy profile. When the atom is placed near a secondary minimum, the mean intensity averaged over its spatial probability density is very low, such that even small intensity variations result in a high uniformity. Near a secondary maximum, the opposite effect occurs, leading to local minima in the uniformity.
The crosstalk η_w shows a oscillating pattern of minima and maxima for a fixed displacement, as already observed in Figure 24, resulting from the secondary maxima and minima of the Airy profile. For larger displacements, this effect becomes less pronounced and occurs for different waists as the light from other neighboring Airy spots starts to illuminate the atom. The crosstalk reaches values of $\eta_w = 10\,\%$ for displacements smaller than the waist of the Airy profile. For larger displacements, the crosstalk exhibits lines of local maxima resulting from the secondary minima of the Airy profile. On these lines of local maxima the intensity of the central spot is very low, while the eight neighboring spots still illuminate the atom. To further assess the suitability of the previously introduced working point, the changes in uniformity and crosstalk caused by atomic displacement are investigated for this case. For the selected waist of $\omega = 1.9$ µm, the corresponding cross sections of Figure 26 are evaluated and the change of uniformity and crosstalk is shown in Figure 27. The atomic displacement increases both the uniformity and crosstalk, reaching up to $27.8\,\%$ and $19.8\,\%$, respectively. For shifts of up to 0.5 µm, the crosstalk remains under $1\,\%$, while the uniformity deviation exceeds the $5\,\%$ mark. At the previously identified mark of 1 µm for the multi-tone profile, the Airy profile exhibits a uniformity of $U_w = 10.8(7)\,\%$ and a crosstalk of $\eta_w = 3.7(1)\,\%$. Therefore, a limit for the misalignment of the trap array relative to the Raman array of 0.5 µm can be defined.




Fig. 26: Two-dimensional plots of the uniformity U_w and the crosstalk η_w for the displacement r of the atom in an Airy profile with waist ω from the center outwards. Additionally, the displacement up to the waist $r = \omega$ is marked in white.




Fig. 27: Uniformity U_w and the crosstalk η_w for an atom moved vertically up to the waist $\omega = 1.9\,\mu\text{m}$ of the Airy profile.

4.5 Beating and Crest factor

With a given set of parameters for the static beam profile, the next step is the simulation of the beating that results from interference of light fields with similar frequencies. The magnitude of the resulting intensity variations determines to which degree multi-tone Top Hat profiles are suitable for quantum gate operations.
The resulting tone frequencies for a frequency width of 0.37 MHz and a frequency offset of 100 MHz in both perpendicular AODs are:

$$f_{x,i} \in \{100.000,\ 100.185,\ 100.370\}\,\text{MHz}, \tag{4.10}$$

$$f_{y,j} \in \{100.000,\ 100.123,\ 100.247,\ 100.370\}\,\text{MHz}. \tag{4.11}$$

The frequency spacings are accordingly:

$$\Delta f_x = \frac{W}{2} = 185\,\text{kHz}, \qquad \Delta f_y = \frac{W}{3} = 123.3\,\text{kHz}. \tag{4.12}$$

The greatest common divisor of the frequency spacings, and therefore the fundamental frequency of the beating spectrum and its corresponding period time, are given by:

$$f_0 = \frac{W}{\text{lcm}(2,3)} = \frac{W}{6} = 61.67\,\text{kHz}, \qquad T_0 = \frac{1}{f_0} = 16.22\,\mu\text{s}, \tag{4.13}$$

so that $\Delta f_x = 3f_0$ and $\Delta f_y = 2f_0$ holds. With $c = 6.316\,\mu\text{m/MHz}$ the spots have pitches $p_x = 1.169\,\mu\text{m}$ and $p_y = 0.779\,\mu\text{m}$ on the rectangular lattice with the full width of $2.337\,\mu\text{m}$. The order of a spot (i, j) with $0 \le i \le 2$ and $0 \le j \le 3$ together with its frequency $f_{i,j}$ are given by:

$$k_{i,j} = 3i + 2j, \qquad f_{i,j} = 200\,\text{MHz} + k_{i,j} \cdot f_0. \tag{4.14}$$

This results in spot orders on the 3×4 grid between 0 and 12 distributed in the following pattern: The twelve spots of the 3×4 grid fall into eleven groups. With $z_{(i,j)} = g_{(i,j)}\, e^{i\phi_{i,j}}$ the

	$j=0$	$j=1$	$j=2$	$j=3$
$i=2$	**6**	8	10	12
$i=1$	3	5	7	9
$i=0$	0	2	4	**6**

Tab. 4.1: Spot orders $k_{i,j}$ of the 3×4 grid created with two perpendicular AODs with $f_0 = 61.67\,\text{kHz}$ and a frequency width of 0.37 MHz.

components of the group field are:

$$\begin{aligned} &H_0 = z_{(0,0)}, \quad H_2 = z_{(0,1)}, \quad H_3 = z_{(1,0)}, \quad H_4 = z_{(0,2)}, \\ &H_5 = z_{(1,1)}, \quad H_6 = z_{(0,3)} + z_{(2,0)}, \quad H_7 = z_{(1,2)}, \quad H_8 = z_{(2,1)}, \\ &H_9 = z_{(1,3)}, \quad H_{(10)} = z_{(2,2)}, \quad H_{12} = z_{(2,3)}, \quad H_1 = H_{11} = 0. \end{aligned} \tag{4.15}$$

H_6 contains the two diagonal spots on the opposite corners $(0, 3)$ and $(2, 0)$ that are $3.305\,\mu\text{m}$ apart. The orders $k = 1$ and $k = 11$ are not occupied and not a part of $H_m(\mathbf{r})$.
The time average contains, in addition to the incoherent sum, the terms for the static interference of the corner pair as already discussed in chapter 2 with Equation 2.42:

$$\langle I \rangle_t = \sum_s g_s^2 + 2\, g_{0,3}\, g_{2,0} \cos(\phi_{x,0} + \phi_{y,3} - \phi_{x,2} - \phi_{y,0})\,. \tag{4.16}$$

Here the tone phases determine the coherent static interference pattern that vanishes for $\Delta\phi = \phi_{03} - \phi_{20} = (\phi_{x,0} + \phi_{y,3}) - (\phi_{x,2} + \phi_{y,0}) = \pm\pi/2$.
A pair of spots separated by $(\Delta i, \Delta j)$ has a beating order d defined as the difference of their spot orders:

$$d = 3\,\Delta i + 2\,\Delta j, \qquad |\Delta i| \le 2, \quad |\Delta j| \le 3, \tag{4.17}$$

and their corresponding distance in the focal plane is given by $\sqrt{(\Delta i\, p_x)^2 + (\Delta j\, p_y)^2}$. The cross term is weighted by the spatial overlap of the spots $g_s(\mathbf{r}) g_{s'}(\mathbf{r})$, so close pairs have a larger contribution on the beating.

An analysis of the temporal variations in the profile intensity for the given parameters reveals rapid oscillations, as shown in Figure 28, with a beating period of $T_0 = 16.22\,\mu s$. Over the beating period, the intensity is spatially varying on the whole profile leaving the center, and thus the atom, dark for several µs. The uniform intensity of the generated multi-tone profile is achieved only in the time average, but not on timescales of light pulses comparable to the beating period. This contradicts the whole purpose of the generated Top Hat profile. If a uniform mean intensity is achieved only for long pulse durations, the multi-tone Top Hat profile offers no advantage over a single Airy profile. The seven phases of the beam profile as remaining degrees of freedom have to be chosen in such a way that the created profile illuminates the




Fig. 28: Oscillating intensity of a 3×4 multi-tone beam profile with a beating period of $T_0 = 16.22\,\mu s$ shown for $t = \{0, T_0/3, 2T_0/3\}$ and normalized over the time average of the atom weighted intensity $\langle I \rangle_t$.

atom in the center for a given pulse duration as uniform as possible. Phases chosen randomly can leave the center dark over several µs and introduce an gradient in the intensity. Reliable gate operations for atoms with spatial thermal fluctuations would be distorted so the phases have to be chosen accordingly. As shown in the appendix section A.1 the condition for a symmetrical intensity profile $I(-\mathbf{r}, t) = I(\mathbf{r}, t) \quad \forall\, t$ is:

$$\varphi_n + \varphi_{N_x-1-n} = c_x \;\; \forall n, \qquad \varphi_m + \varphi_{N_y-1-m} = c_y \;\; \forall m \tag{4.18}$$

A secondary condition for the optimization of the phases can be found using the Crest factor C [26]. The Radio Frequency (RF) multi-tone signal $s(t)$ creating the acoustic wave inside the acousto-optical crystal and subsequently the multi-tone profile can be characterized with the Crest factor defined as:

$$C = \frac{\max_t |s(t)|}{\mathrm{rms}_t[s(t)]} \tag{4.19}$$

A limited Crest factor imposes an upper bound for the maximum RF amplitude and consequently the peak RF power applied to the AOD. A high Crest factor limits the achievable mean power level of the AOD, thereby reducing the diffraction efficiency for each spot. Setting a limit of $C = 2.5$ for both axis as a condition for the optimization of the phases leads to:

$$\varphi_x = [0°, 12°, 24°], \quad \varphi_y = [0°, 98°, 16°, 114°].$$

With this the Crest factors are $C_x \approx 2.449$ and $C_y \approx 2.196$. The condition for a symmetrical intensity profile is fulfilled with $c_x = 24°$ and $c_y = 114°$ while for Equation 4.16 the static

spatial interference is minimized.
Table 4.2 lists all beating orders and their configurations for the 3×4 multi-tone profile with the optimized phases. The last column gives the contribution of each order, $\sigma_d/\langle I\rangle_t$ with $\sigma_d = \sqrt{2|D_d|^2}$ and $\langle I\rangle_t = D_0$, as an rms over the spot square ($2.34\,\mu m \times 2.34\,\mu m$) as $U_{td} = \left\langle \sigma_d^2/\langle I\rangle_t^2 \right\rangle_R^{1/2}$, so that it is defined over the same region R as the spatial uniformity U_h. The beating order $d = 0$ has to be excluded from the evaluation of the beating because its constant intensity contributes to the mean intensity but has no oscillating component.

d	f_{beat}(kHz)	pairs	$(\Delta i, \Delta j)$	distance (µm)	U_{td} (%)
0	0	1	$(2,-3)$	3.31	–
1	61.7	10	$(1,-1)$, $(-1,2)$	1.40, 1.95	20.0
2	123.3	11	$(0,1)$, $(2,-2)$	0.78, 2.81	40.4
3	185.0	10	$(1,0)$, $(-1,3)$	1.17, 2.61	**51.9**
4	246.7	9	$(0,2)$, $(2,-1)$	1.56, 2.46	20.4
5	308.3	6	$(1,1)$	1.40	18.8
6	370.0	7	$(2,0)$, $(0,3)$	2.34, 2.34	16.1
7	431.7	4	$(1,2)$	1.95	6.9
8	493.3	3	$(2,1)$	2.46	3.2
9	555.0	2	$(1,3)$	2.61	6.2
10	616.7	2	$(2,2)$	2.81	5.4
11	678.3	0	–	–	–
12	740.0	1	$(2,3)$	3.31	1.8

Tab. 4.2: Beating orders for a 3×4 multi-tone profile at the working point with $f_0 = 61.67$ kHz together with the distance of the corresponding spot pairs and their contribution to the time dependent uniformity, calculated as an Root Mean Square (RMS) over the spot square R, for the tone phases $\varphi_x = [0°, 12°, 24°]$ and $\varphi_y = [0°, 98°, 16°, 114°]$ used in this work.

Furthermore, it vanishes for the phase configuration chosen previously according to Equation 4.16. The strongest contribution has the beating order $d = 3$ with $51.9\,\%$, produced by the nearest neighbors along x, followed by the nearest neighbors along y at $d = 2$ with $40.4\,\%$. The diagonal next neighbors with the beating orders $d = 1$ and 5 have with around $20\,\%$ a comparable part of the beating. The higher the beating order increases, the smaller its contribution gets, since the spatial overlap of the spots decreases. The order $d = 12$ is produced by a single pair of corner spots has the lowest contribution to the beating. Its magnitude remains no matter how the phases are chosen since destructive interference with another pair of spots is not possible. The total time dependent uniformity is then given as:

$$U_t = \left\langle U_t(\mathbf{r})^2 \right\rangle_R^{1/2} = \left\langle \frac{\sigma_I^2}{\langle I \rangle_t^2} \right\rangle_R^{1/2} = \left(\sum_{d>0} \left\langle \frac{\sigma_d^2}{\langle I \rangle_t^2} \right\rangle_R \right)^{1/2} = \left(\sum_{d>0} (U_{t_d})^2 \right)^{1/2} = 76.7\,\%. \tag{4.20}$$

Two beating frequencies lie close to the trap resonances. For $d = 2$, the beating frequency $f_{\text{beat}} = 123.3\,\text{kHz}$ lies $2.5\,\text{kHz}$ above the parametric resonance at $2\nu_r = 120.8\,\text{kHz}$. For $d = 1$, $f_{\text{beat}} = 61.7\,\text{kHz}$ lies $1.3\,\text{kHz}$ above the trap resonance at $\nu_r = 60.4\,\text{kHz}$. Consequently, long pulses spanning multiple beating periods could cause heating of the addressed atom, potentially leading to atom loss and reduced fidelity in multi-qubit gate operations. For pulse durations much shorter than the beating period, however, the spectral broadening associated with the finite pulse duration can reduce the risk of resonant heating. For example, a pulse duration of $T_0 = 1\,\mu\text{s}$ corresponds to a spectral width of approximately $\delta\nu = 1\,\text{MHz}$, which is about 16.5 times the trap frequency ν_r.
The high time dependent uniformity as a direct way to measure the impact of the intensity variations confirms the non-uniformity of the generated multi-tone profile observed in Figure 28. Single-site addressing with such a beating has a clear disadvantage compared to the use of a single Airy profile per atom position.

4.6 Pulse area with beating

For Rabi oscillations or general the excitation of atoms between two states, the the image of the Bloch sphere introduced in chapter 2 can be used. For a light pulse with a time-dependent intensity, the angle Θ, also known as the pulse area, which characterizes the population transfer between the two states, is given by:

$$\theta(\mathbf{r}, t_0, T_p) = \int_{t_0}^{t_0+T_p} \Omega(\mathbf{r}, t)\, \mathrm{d}t \tag{4.21}$$

with t_0 the starting time of the pulse and T_P being the pulse length. For a two photon process the intensity I of the whole beam is split between the two beams with the weight β, such that their respective intensities are βI and $(1-\beta)I$. These two intensities drive transitions between $|F{=}2, m\rangle \leftrightarrow |F{=}3, m\rangle$ via the $5P$ manifold of ^{85}Rb [2]. The single-photon Rabi frequency $\Omega_{q,i}$ of beam q coupling to an intermediate state $|i\rangle$ is given by $\Omega_{q,i} = d_i E_q/\hbar$. Hereby d_i is the transition dipole matrix element from the ground state $|g\rangle$ to the intermediate state $|i\rangle$. Using the relation $I_q = \frac{1}{2}\varepsilon_0 c E_q^2$ [27] it takes the form:

$$\Omega_{q,i}^2 = \frac{2\, d_i^2}{\varepsilon_0 c\, \hbar^2}\, I_q \equiv d_i^2\, \kappa\, I_q, \qquad \kappa = \frac{2}{\varepsilon_0 c\, \hbar^2}. \tag{4.22}$$

For a large detuning the intermediate states are eliminated adiabatically, as already discussed in subsection 2.2.2. Each of these excited states contributes to the Rabi frequency of the two-photon process:

$$\Omega = \sum_i \frac{\Omega_{1,i}\, \Omega_{2,i}}{2\Delta_i} = \underbrace{\kappa\sqrt{\beta(1-\beta)} \sum_i \frac{d_{2i}\, d_{3i}}{2\Delta_i}}_{C_{\text{rabi}}}\, I = C_{\text{rabi}} I. \tag{4.23}$$

Here, the contributions from all relevant excited states are incorporated into the Rabi constant C_{rabi}. Thus the effective Rabi frequency is directly proportional to the laser intensity. An intermediate state is given for example by a hyperfine level of the $5P$ manifold,

$$|i\rangle = |5P_{J'}, F', m'\rangle \tag{4.24}$$

with $J' = \frac{1}{2}$ for D_1 line that has $F' = 2, 3$ and $J' = \frac{3}{2}$ for D_2 line that has $F' = 1, 2, 3, 4$ [2]. $d_{2i} = \langle i|\hat{d}|F{=}2, m\rangle$ and $d_{3i} = \langle i|\hat{d}|F{=}3, m\rangle$ are the dipole matrix elements, and Δ_i is the detuning of the laser from the specific intermediate state $|i\rangle$. Δ is the global detuning of the laser beams relative to the center frequency of the D_1 line of ^{85}Rb [2]. The detuning Δ_i can be calculated with the center frequency of the corresponding line $\nu_{J'} \in [\nu_{D_1}, \nu_{D_2}]$ and the hyperfine splitting $\mathrm{hfs}(J', F')$ of each intermediate energy level relative to it:

$$\Delta_i = 2\pi \left[\Delta + (\nu_{D_1} - \nu_{J'}) - \Delta_{\text{hfs}}(J', F')\right]. \tag{4.25}$$

The calculations above are evaluated within a python based simulation [25] with atomic data from the ARC package [28]. The resulting Rabi constant is then calculated for a detuning of $\Delta = 50\,\mathrm{GHz}$:

$$C_{\text{rabi}} = 11.66\, \frac{\mathrm{rad\,m^2}}{\mathrm{W\,s}}. \tag{4.26}$$

With the previously chosen set of phases, a symmetric beam profile can be achieved, resulting in a symmetric spatial distribution of the pulse area. Using the proportionality between the Rabi frequency and the intensity, the pulse area can be expressed as:

$$\theta(\mathbf{r}, t_0, T_p) = \int_{t_0}^{t_0+T_p} \Omega(\mathbf{r}, t)\,\mathrm{d}t = C_{\text{rabi}} \int_{t_0}^{t_0+T_p} I(\mathbf{r}, t)\,\mathrm{d}t. \tag{4.27}$$

Up to this point, the simulated beam profiles are normalized and do not include physical units. To obtain the physical intensity distribution, a scaling factor s is introduced, which relates the normalized profile to the total power P of the time-averaged Top Hat profile:

$$P = \int \langle I(\mathbf{r})\rangle_t, \mathrm{d}^2 r = s \int \langle \tilde{I}(\mathbf{r})\rangle_t, \mathrm{d}^2 r \equiv s\tilde{P}_{\text{prof}}, \qquad \Longrightarrow \qquad s = \frac{P}{\tilde{P}_{\text{prof}}}. \tag{4.28}$$

Here $\tilde{P}_{\text{prof}}$ represents the spatially integrated normalized intensity profile. With the scaling factor the intensity can be expressed as $I(\mathbf{r}, t) = s\tilde{I}(\mathbf{r}, t)$ and the pulse area is accordingly:

$$\theta(\mathbf{r}, t_0, T_p) = C_{\text{rabi}}\, s \int_{t_0}^{t_0+T_p} \tilde{I}(\mathbf{r}, t)\,\mathrm{d}t = C_{\text{rabi}}\, \frac{P}{\tilde{P}_{\text{prof}}} \int_{t_0}^{t_0+T_p} \tilde{I}(\mathbf{r}, t)\,\mathrm{d}t. \tag{4.29}$$

With the definition of $\tilde{P}_{\text{prof}}$ the pulse area is given by:

$$\boxed{\theta(\mathbf{r}, t_0) = C_{\text{rabi}}\, P\, \frac{\displaystyle\int_{t_0}^{t_0+T_p} \tilde{I}(\mathbf{r}, t)\,\mathrm{d}t}{\displaystyle\int \langle \tilde{I}\rangle_t\, \mathrm{d}^2 r}} \tag{4.30}$$

The time integral is the only part that still depends on the beating. Inserting the Fourier series $\tilde{I}(\mathbf{r}, t) = \sum_d D_d(\mathbf{r})\, e^{i2\pi d f_0 t}$ into Equation 4.30, the contribution of each order is:

$$\int_{t_0}^{t_0+T_p} e^{i2\pi d f_0 t}\,\mathrm{d}t = \frac{e^{i2\pi d f_0 (t_0+T_p)} - e^{i2\pi d f_0 t_0}}{i\,2\pi d f_0}. \tag{4.31}$$

Extracting the phase factor $e^{i2\pi d f_0 (t_0+T_p/2)}$ and using $e^{ix} - e^{-ix} = 2i\sin(x)$

$$= e^{i2\pi d f_0 (t_0+T_p/2)}\, \frac{e^{i\pi d f_0 T_p} - e^{-i\pi d f_0 T_p}}{i\,2\pi d f_0} = e^{i2\pi d f_0 (t_0+T_p/2)}\, \frac{\sin(\pi d f_0 T_p)}{\pi d f_0}. \tag{4.32}$$

Here the definition of $\mathrm{sinc}(z) = \sin(\pi z)/(\pi z)$ can be used:

$$\int_{t_0}^{t_0+T_p} \tilde{I}\,\mathrm{d}t = T_p \sum_d D_d(\mathbf{r})\ \mathrm{sinc}(d f_0 T_p)\, e^{i2\pi d f_0 (t_0+T_p/2)}. \tag{4.33}$$

The equation for the pulse area used in the simulation is then given by:

$$\theta(\mathbf{r}, t_0, T_p) = \frac{C_{\text{rabi}}\, P\, T_p}{\tilde{P}_{\text{prof}}} \sum_d D_d(\mathbf{r})\ \mathrm{sinc}(d f_0 T_p)\, e^{i2\pi d f_0 (t_0+T_p/2)}. \tag{4.34}$$

The calculation for $\tilde{P}_{\text{prof}}$ is done in section A.3. The simulation for the pulse area of the 3×4 multi-tone Top Hat profile is conducted for a Profile power of $P = 10\,\mu\mathrm{W}$, a pulse duration




Fig. 29: Simulated pulse area of a multi-tone Top Hat profile with $C_{\text{rabi}} = 11.66\,\text{radm}^2/\text{Ws}$, $P = 10\,\mu\text{W}$, $T_p = 1\,\mu\text{s}$ and $t_0 = 15.4\,\mu\text{s}$. Depicted is just the central area in which the atom has the highest spatial probability density as marked by the 3σ region.

of $T_p = 1\,\mu\text{s}$ and a starting time of $t_0 = 15.4\,\mu\text{s}$. The results are shown in Figure 29 and are focused around the spatial probability density of the atom within the 3σ region.
The maximum pulse area at the center of the profile is $\theta_{\text{max}} = 5.55\pi$, while the minimum value within the 3σ region is $\theta_{\text{min}} = 5.4\pi$. This corresponds to a nearly uniform pulse area with a deviation of 2.8%.
The laser pulse can be generated in an experiment using an Acousto-Optical Modulator (AOM) as a switch in the beam path. Triggered correctly, light can be diffracted and reach the atoms. The timing of the trigger is essential for a desired pulse area. For different starting times t_0 the resulting pulse area is averaged over the spatial probability density of the atom and shown in Figure 30 together with the corresponding intensity. Pulse area and intensity exhibit the same behavior but have a small offset from one another. A global maximum in the pulse area is visible for $t_0 = 10.2\,\mu\text{s}$ with $\theta = 6.8\pi$. In this case the the spatial deviation of the pulse area is with more than 20% substantially higher than in Figure 29 with $t_0 = 15.4\,\mu\text{s}$ and therefore not preferred. A potential error in the AOM-trigger of t_0 could cause a deviation in the mean pulse area $\langle\theta\rangle/\pi$ of 65%. In general a compromise has to be found for a pulse trigger that exhibits a small enough mean pulse area deviation while at the same time having a uniform spatial distribution in its center. The length of the light pulses can therefore not be chosen arbitrary since for longer pulses it must be ensured that light is still illuminating the atom. Otherwise longer pulse durations do not change the accumulated pulse area. This is posing as a restriction for the creation of Rabi oscillations or gate operations on certain time-scales. Consequently, in addition to calibrating the spatial alignment of the light with respect to the atoms, a precisely timed trigger for the pulses is needed. Although in principle this is feasible, the use of a multi-tone profile is therefore more complex than illumination with a single Airy spot. The Airy profile does not depict spatial or time-dependent interference and therefore arbitrary pulse durations are possible to drive Rabi oscillations or gate operations.




Fig. 30: Pulse area of a $T_p = 1\,\mu s$ pulse for the 3×4 multi-tone profile at $P = 10\,\mu W$, all quantities averaged over the spatial probability density of the atom. Top: intensity $I(t)$ over one beating period, normalized to its time average. The red line marks the start $t_0 = 15.4\,\mu s$ of the pulse, the shaded area its duration T_p. Center: pulse area $\langle\theta\rangle/\pi$ as a function of the start time t_0 over one beating period with the red marked 15.4 µs. Bottom: Enlarged section around $t_0 = 15.4\,\mu s$, showing the deviation of the pulse area caused by an error in the trigger time. Within $\pm 1\,\mu s$ the pulse area deviates by up to 65 %.

4.7 Validation with the test setup

To verify the simulation results, the test setup previously shown in Figure 13 is used without the Beam Shaper. A disadvantage of this setup is the beam waist in the focal plane behind the Lens Optics Objective. According to Equation 3.4, the expected beam waist is $\omega = 1.15\,\mu m$. The measured waist of a single spot in the focal plane is $\omega = 1.8\,\mu m$. This deviation can be attributed to the beam being truncated by the aperture of the AOD housing, resulting in an insufficient beam size in front of the telescope and, consequently, an excessive beam waist in the focal plane as already observed for the test setup with the Beam Shaper in chapter 3. Since a new optical setup for the whole Raman laser system is needed nonetheless, this test setup will not be used in the experiment either way.
Since using the same number of tones in both dimensions leads to static spatial interference along the anti-diagonals, an $N \times (N+1)$ configuration with $N = 3$ tones, was used throughout the time-independent simulations and the beating analysis as discussed in chapter 2. This limitation on the choice of the number of tones is to be validated by taking an image of a $N \times N$ multi-tone beam profile. This image is then compared with a simulation of the coherent superposition of the corresponding spots, conducted with a Python-based repository [25]. The taken image of the multi-tone profile consisting of 6×6 tones with a frequency width of 0.5 MHz is shown in Figure 31. The symmetric structure of the Top Hat profile is no longer visible in the measured image. Instead, a bright diagonal stripe and an additional side structure below appear. The measured profile shares some features with the simulation, which also predicts a prominent diagonal stripe resulting from the spatial interference of the individual spots. The two profiles differ in the visibility of the square structure. While the simulation retains the square form at the four corners, with the central region dominated by the diagonal stripe, this structure is no longer seen in the measurement. The additional side structure observed in the measurement is not reproduced by the simulation and may therefore originate from effects caused by the AOD. This result proves the necessity to chose different numbers of tones for generating uniform intensity profiles in a multi-tone scheme. Otherwise spatial interference would distort the resulting profile and the advantage of a Top Hat profile is lost.




Fig. 31: Right: Image of the beam profile with 6×6 tones and $W = 0.5$ MHz created with the test setup. A bright diagonal stripe and a small side structure are visible. Left: Simulated image with the same parameters. A tilted square with a dominant diagonal stripe in its center is visible.

To verify whether beating occurs in the generated multi-tone Top Hat profiles, a test image is taken with a camera. The image represents a temporal averaging of the beating over the exposure time T_0:

$$\langle I(r,t)\rangle = \frac{1}{T_0}\int_0^{T_0} I(r,t)dt \tag{4.35}$$

To resolve the time-dependent intensity variations caused by the beating and obtain a high contrast within the taken image, the exposure time of the camera must be shorter than the beating period to avoid averaging over over multiple beating periods. Additionally the camera itself needs a global shutter so all pixels are illuminated by the same period sequence of the beating. A rolling shutter in combination with long read out times could generate an image over several periods with no distinct information of the beating. The used camera (CM3-U3-13S2M-CS) has a minimal exposure time of 45.6 µs and the needed global shutter. For the test image the two perpendicular AODs are used with an achromatic lens $f_1 = 45$ mm as shown in Figure 32.
The optimized multi-tone profile has a beating period time of $T_0 = 16.22$ µs and can therefore not be examined with the available camera. Since another camera with a shorter exposure time and a rolling shutter is not available, the beam profile has to be adapted. The parameters of the profile are chosen such that the beating period is with 100 µs more than twice the minimum exposure time of the camera. Therefore a profile is created with $N_x = 13$ and $N_y = 14$ tones with a frequency width of 1.56 MHz. The results of the simulation and the corresponding measurement are shown in Figure 32. The simulation on the left shows four bright diagonal stripes extending across the entire profile. Small-scale substructures are also visible and may originate from the side structures of the individual Airy profiles. The peak-to-valley value is calculated in the central area of the profile with:

$$PV = \frac{I_{\text{max}} - I_{\text{min}}}{\langle I\rangle}. \tag{4.36}$$

The obtained peak-to-valley value in the simulation is $PV_{\text{sim}} = 68.1\%$. The measurement on the right exhibits the same diagonal stripes as the simulation, although their positions are shifted. This difference arises because the image was taken manually rather than using a synchronized trigger, as would be provided by an AOM. Additionally, the substructures are much more pronounced in the measurement than in the simulation. These structures are identified as the single spots of the profile since 13×14 equally spaced structures can be identified stretching over the whole image. The peak-to-valley value of the taken image is $PV_{\text{im}} = 59.3\%$. The difference of almost 10% between simulation and measurement arises from a lower intensity maximum in the taken image, possibly caused by the substructure of the single spots. The overall agreement between the measured and simulated profiles provides strong validation of the simulation results for the temporal beating.




Fig. 32: Schematic of the setup used for measuring the beating of the multi-tone Top Hat profiles.




Fig. 33: Left: Simulated image of the beating of a 13×14 multi-tone profile with a frequency width of 1.56 MHz for a exposure time of 45.6 µs. Dominant diagonal stripes are visible. Right: Taken image of the beating with the same parameters. The measurement also shows diagonal stripes and is in good agreement with the theoretical simulation.

To evaluate the beating of a 3×4 multi-tone profile with the optimized parameters of $W =$ 0.37 MHz and the chosen phases $\varphi_x = [0°, 12°, 24°]$ and $\varphi_y = [0°, 98°, 16°, 114°]$, the frequency spectrum is measured with a photodiode (DET10A/M). Since the future setup is not yet built, the same setup as before for the image of the beating Figure 32 is used. The photodiode is placed in the focal plane of the lens so the whole beam profile is measured.
Additionally a simulation with a Python-based repository [25] of the beating orders is conducted that differs from the one shown in Table 4.2. This is a result of the measurement method itself since a photodiode first integrates the intensity over the whole detector area and then the variation of the different frequency components can be determined. For an ideal measurement in the focal plane of the lens the contribution of each beating order is simulated as:

$$U_{t_d}^{sim} = \frac{\sqrt{2}|\int D_d \, \mathrm{d}A|}{\int D_0 \, \mathrm{d}A}. \tag{4.37}$$

For the whole detector area this results in lower contributions of the different beating orders since each frequency has a lower relative contribution to the whole signal. The simulation conducted for Table 4.2 based on Equation 2.45 calculates the intensity variations for each position in the profile and then the squared values are averaged over the whole profile. With this calculation method every intensity variation has a positive contribution and does not average out as in Equation 4.37. To measure the beating, this method of evaluation could be implemented using a camera to acquire a time-resolved sequence of spatially resolved beam profile images over the period time of the beating. Necessary for the camera-based measurement is a exposure time much shorter than the period time of the beating. Since this limiting factor could not be overcome, as already discussed for Figure 33, the measurement with the photodiode is performed instead.
In the simulation Gaussian spots with the measured diameter $d = 12.8$ µm are assumed. For the measurement the mean voltage signal $\bar{U}$ is measured as $\bar{U} = 4.90$ mV and then the peak amplitude of the beating order resulting from the Fourier Transform $\hat{U}_d$ is determined. The

contribution of each beating order of the measurement is then calculated as:

$$U_{td}^{\text{meas}} = \hat{U}_d/(\sqrt{2}\,\bar{U}) \tag{4.38}$$

The resulting spectrum of the beating orders is shown in Figure 34 together with the simulated spectrum. Additionally an overview of each beating order is given in Table 4.3.
For $d = 2$ and $d = 3$ resulting from vertically and horizontally adjacent spots, the beating orders have the highest contribution to the beating in the simulation and the measurement and are in good agreement to each other. For $d = 1$ and $d = 5$ resulting from diagonally adjacent spots, this also holds true. The main difference between measurement and simulation is found in the orders $d = 4$ and $d = 6$ resulting from the spot pairs separated by two sites vertically/horizontally. The measurement is significantly higher than the simulation which can be explained with a higher overlap of the corresponding spots caused by side structures not included in a simple Gaussian model for the spots in the simulation. For higher orders $d > 6$ caused by more distant spot pairs the simulation shows little to no beating with those frequencies while the measurement still depicts oscillations. This also supports the possibility of side structures not occurring for Gaussian spots. Deviations between simulation and measurement may also arise from differences in the size of the individual spots. The simulation assumes ideal Gaussian profiles with a diameter of 12.8 µm in the focal plane of the lens. If the photodiode is not positioned exactly in the focal plane, the actual beam diameter at the detector may differ from the simulated value. Additionally, partial clipping of the beam profile by the active area of the photodiode may lead to further differences between the measured and simulated results.
By combining the contributions of all beating orders, the uniformity of the entire beam profile can be calculated. The resulting values, $U_t^{\text{meas}} = 35.3\%$ and $U_t^{\text{sim}} = 36.5\%$, show good agreement between measurement and simulation, supporting the validity of the simulation model.
Additionally, with the spot diameter and the number of tones, this measurement method provides information about the spatial intensity variations without requiring camera-based imaging of the beam profile.

d	f_{beat} (kHz)	pairs	$\hat{U}_d$ (mV)	U_{td}^{meas} (%)	U_{td}^{sim} (%)
1	61.7	10	0.284	4.1	4.4
2	123.3	11	1.374	19.8	20.7
3	185.0	10	1.739	**25.1**	**28.2**
4	246.7	9	0.928	13.4	8.3
5	308.3	6	0.217	3.1	4.1
6	370.0	7	0.263	3.8	0.5
7	431.7	4	0.142	2.0	1.7
8	493.3	3	0.013	0.2	0.1
9	555.0	2	0.053	0.8	0.1
10	616.7	2	0.021	0.3	0.0
11	678.3	0	0.002	0.0	–
12	740.0	1	0.010	0.2	0.0
total $U_t^{\text{PD}} = \sqrt{\sum_d U_{td}^2}$				35.3	36.5

Tab. 4.3: Beat orders of the 3×4 grid measured with a photodiode in the focal plane of the $f = 45$ mm lens. Shown are is the peak amplitude of the beat line $\hat{U}_d$, its relative rms contribution. U_{td}^{meas} and the simulated contribution U_{td}^{sim} for Gaussian spots with the beam diameter $d = 12.8$ µm.




Fig. 34: Spectrum of the beating orders of a 3×4 profile with $W = 0.37$ MHz in the focal plane of a lens $f = 45$ mm measured with a photodiode and compared with the simulation. Up to $d = 12$ the measured spectrum contains frequencies thath do not appear in the simulation.

4.8 Conclusion

With a simulation performed for two different calculation metrics and their combination, a comparison of the time independent multi-tone approach and the single Airy spot is shown in table 4.4. The working points differ in terms of the used beam waist within the atomic plane with 1.04 µm and 1.9 µm. Switching between the two approaches requires no changes of the optical hardware. Only an adjustment of the beam waist using the Beam Expander in front of the two perpendicular AODs, as in the test setup shown in Figure 13, and a switch between single-tone and multi-tone RF signals are necessary.
A direct comparison of the hard metrics in regard of the uniformity is not suitable here, since

Parameter	Multi-tone	Single spot
Beam waist ω	1.04 µm	1.9 µm
Profile width W	2.34 µm	—
Amplitude ratio r_x	0.97	—
Amplitude ratio r_y	1.16	—
Hard uniformity U_h	3.56(3) %	13.9(1) %
Hard crosstalk η_h	8.40(5) %	12.5(1) %
Weighted uniformity U_w	0.43(5) %	1.06(15) %
1 µm shift U_w	4.1(3) %	10.8(7) %
Weighted crosstalk η_w	1.40(3) %	0.15(4) %
1 µm shift in η_w	3.5(1) %	3.7(1) %

Tab. 4.4: Comparison of the selected working points for the multi-tone and single-spot approaches, including the parameters used to generate each profile and the resulting uniformity and crosstalk, as well as their sensitivity to relative displacements between the beam profile and the dipole trap.

the single Airy spot a circle with radius 1 µm is used, while for the multi-tone profile the calculation area is given through the spot square of 2.34 µm width. For the crosstalk η_h, on the other hand, both calculation areas are identical. The multi-tone approach has a lower crosstalk by $4.1\,\%$. The atom-weighted case of the multi-tone approach has with $1.40(3)\,\%$ a crosstalk almost ten times as high as the single spot approach with just $0.15(4)\,\%$. Since this result is based on the spatial probability density of the atom rather than purely geometric considerations, it is more meaningful and poses a clear advantage of the single spot approach compared to the use of a multi-tone profile. The atom-weighted uniformities are of the same order of magnitude, although the single-spot profile exhibits a more than two times higher uniformity of $1.06(15)\,\%$ compared to $0.43(5)\,\%$ for the multi-tone profile, giving the latter an advantage. A displacement of the atom relative to the multi-tone profile causes a much smaller increase in the uniformity and the crosstalk, as intended by its design. For displacements of $r = 1$ µm the uniformity increases up to $4.1\,\%$ for a multi-tone profile, while for the single Airy profile the increase is $10.8\,\%$. For the crosstalk, the difference of the two approaches is with $3.5\,\%$ and $3.7\,\%$ almost identical. Except for the atom-weighted crosstalk, these numbers are either in the same order of magnitude or favorable for a multi-tone profile. The use of a single Airy profile still remains a possibility, since it does not pose the risk of static interference or a strong beating since no spots directly overlap.

For the selected working point of the multi-tone profile, a simulation of the beating for the superimposing of laser beams was conducted and partially validated for the frequency spectrum and the spatial intensity distribution. The beating has a period time of 16.22 µs and the intensity shows variations with differences up to four times its time average. The whole profile has a time-dependent uniformity of $U_t = 76.7\,\%$ inside its spot square, which contradicts the purpose of generating uniform intensity profiles with a multi-tone AOD on time scales of the beating. For longer illumination times, as required for applications such as optical pumping, the time-averaged profile takes the desired Top Hat shape. With the right choice of phases for each tone, the profile can be symmetrical with regard to its center, allowing the atom to be illuminated more uniformly on shorter time scales. To use multi-tone profiles on time scales in the order of the beating period time, a timed trigger is necessary. With a right timed trigger, the spatial distribution of the pulse area is uniform in its center around the assumed position of the atom. Nevertheless this requires stable beam pointing for the dipole trap holding the atom relative to the profile center and offers no advantage compared to a single Airy profile. Additionally the length of light pulses is limited due to the beating, posing as a restriction for the creation of Rabi oscillations or gate operations on certain time-scales. The use of an Airy profile does not lead to beating on the other hand. Even on short time scales the atom can be illuminated without the need to calibrate an additional trigger and the length of potential light pulses can be chosen as required for the intended Rabi oscillations. Even though the uniformity of an Airy profile is worse compared to a averaged multi-tone profile and the Airy profile can only be approximated as uniform close to its center, it is the preferable choice for single-site addressing. With a lower atom-weighted crosstalk and no spatial or time dependent interference, the advantages of a single Airy profile outweigh the disadvantages compared to a multi-tone Top Hat profile.

5 Planning of an optical setup

A next step is the construction of a modular Raman laser board that integrates the existing global addressing scheme described in [7] in a more compact form, alongside a new setup for single-site addressing, which has not previously been available in the Quantum Information Processing System (QUIPS)-C experiment.
Combining both setups into one will make the whole system more efficient for reducing lengths of optical paths. Spatial restrictions are set due to the already placed optical setups on the experiment table. The whole setup is placed on an aluminum board which allows for construction work to be performed in a different laboratory. The dimensions of the board are 750 mm $\times$ 850 mm.
A schematic of a new potential optical setup is shown in Figure 35. The laser light is provided by the Raman laser system built in [5] and integrated into the experimental setup in [6]. With this system, the necessary frequency shift is generated for the two-photon Raman transition. In both cases, the light is coupled out of the fiber couplers and filtered to ensure the desired polarization and wavelength. A small fraction of the light is then directed onto a photodiode for intensity stabilization and monitoring. The part of the setup used for global addressing is a rearrangement of [7] with the goal to reduce the length of the optical path between the setup itself and the vacuum chamber. The laser beam for the global addressing passes through a Beam Expander and a diffractive Beam Shaper. It is then magnified by a telescope to achieve the required beam diameter before being focused by the Lens Optics Objective, thereby generating a square Top Hat profile in the atomic plane that covers a large area of the atomic grid.
The laser light for the single-site addressing is passing through a Beam Expander. To improve the imaging quality, a $1:1$ telescope is planned to be placed between the two perpendicular Acousto-Optical Deflector (AOD)s that follow afterwards. This allows the first lens of the subsequent telescope, which determines the scanning range according to Equation 3.3, to be positioned at a distance equal to its focal length $f_1 = 75\,\text{mm}$ from the second AOD. In a future setup, alternative $1:1$ imaging systems consisting of multiple lenses, similar to the Lens Optics Objective, could be considered to reduce spherical aberration. The telescope is designed with focal lengths of $f_1 = 75\,\text{mm}$ and $f_2 = 750\,\text{mm}$, resulting in a scanning range of $r_{\text{max}} = 227.5\,\mu\text{m}$, as already discussed in chapter 4. All lenses are positioned such that the distance between adjacent lenses equals the sum of their respective focal lengths. Although alternative focal lengths could provide a larger scanning range according to Equation 3.3, spatial constraints must be considered, as they may prevent the lenses from being positioned at the required distances. After passing through the telescope, the light is combined through a Polarizing Beam Splitter (PBS) with the laser beam used for global addressing. A camera at the remaining port of the PBS allows the beam quality of both setups to be monitored. Afterwards, the beam passes through a Dichroic Mirror (DM), which is used to couple in light from a Rydberg laser system, and a $\lambda/4$ plate before the combined light is imaged through the glass window into the vacuum chamber by the Lens Optics Objective. For the two-photon process, the light inside the vacuum chamber is then circularly polarized.
An advantage of the single-site addressing setup is the flexibility to switch between the different addressing methods with minimal additional effort. Switching from multi-tone Top Hat profiles

to single Airy profiles requires only adjusting the beam waist using the variable Beam Expander and driving each AOD with a single tone.




Fig. 35: Schematic of a new potential laser system for the beam shaping of the Raman laser beams. It consists of a global addressing scheme using a Beam Shaper and a part for single-site addressing with two perpendicular AODs. The laser beams are provided by the same laser board with two fiber-couplings and are then both shaped for their respective purpose and superimposed before reaching the vacuum chamber symbolized by the glass window.

6 Conclusion and outlook

In this work several approaches for the single-site addressing of ^{85}Rb with an uniform intensity profile have been examined. Initially, the use of a Beam Shaper in a test setup yielded promising results with diameters of less than 10 µm as specified by the manufacturer. The diameter of these profiles is larger than expected, as the beam size approaches the diffraction limit, where the empirical relation provided by the manufacturer is no longer applicable. Additionally, the recorded images show an elliptical beam profile that could not be eliminated by optical adjustments. Using an Acousto-Optical Deflector (AOD) in combination with a Beam Shaper distorts the beam profile even further. In combination with an increased beam waist due to truncation at the aperture of the AOD housing, the resulting profile is not reproducible and suitable for single-site addressing.
The next approach for the generation of Top Hat profiles used the AOD to superimpose multiple deflected spots. The frequency shift on each spot induced by the AOD made it necessary to use $N \times N + 1$ spots to avoid spatial interference. To determine the parameters for a multi-tone Top Hat profile, time independent simulations were conducted for a profile consisting of 3×4 spots. A linear dependence between the spot waist ω and the frequency width W of the profile was found to minimize the uniformity and the crosstalk. Additionally, the intensity amplitude ratios $r_{x,y}$ of the outer to the inner amplitudes could be determined for both dimensions. The optimal parameters are $N_x = 3$, $N_y = 4$, $\omega = 1.04\,\mu\text{m}$, $W = 0.37\,\text{MHz}$, $r_x = 0.97$ and $r_y = 1.16$. Afterwards, a simulation for these parameters regarding the temporal beating of the overlapping spots was conducted. The temporal beating results in strong spatial intensity fluctuations, which can negate the advantages of the intended Top Hat profile for short pulse durations. With a beating period of $T_0 = 16.22\,\mu\text{s}$, a time dependent uniformity of $U_t = 76.7\%$ for the whole profile was found. For longer pulse durations, on the other hand, the rapid temporal variations are averaged out, causing the measured intensity profile to approach the desired Top Hat structure. This could be beneficial for longer addressing times required for optical pumping. With a symmetric intensity profile achieved through an appropriate choice of phases and an additional timed trigger, single-site addressing for quantum gate operations remains feasible, even for short pulse durations according to the simulation. To avoid spatial and time-dependent interference, the use of a single Airy spot with $\omega = 1.9\,\mu\text{m}$ is preferred. Compared to a multi-tone Top Hat profile, this approach yields a slightly worse, but still satisfactory, uniformity and crosstalk for the whole profile, while the crosstalk weighted with the spatial probability density of the atom is more favorable for a single Airy profile.
Based on these results for generating Top Hat profiles near the diffraction limit, the next step is to build a laser system to enable single-site addressing. The existing global excitation scheme [7] is to be combined with a local addressing setup, consisting of two perpendicular AODs. The proposed setup also offers the flexibility to switch between the different addressing methods. With such a setup, two-photon Raman transitions between the hyperfine ground states of ^{85}Rb can be driven globally across the entire atomic grid or selectively at individual sites. As a first step, Rabi oscillations can be driven to determine the pulse durations required for future single-qubit gate operations for a given set of beam parameters.

Appendix

The following notations are used for the performed calculations:

N_x, N_y	number of tones per axis, indices n, m
W	frequency span per axis, tone spacing $\Delta f = W/(N-1)$
φ_n, φ_m	tone phases, free parameters at the AWG
a_n, b_m	tone *power* weights, $A_s = \sqrt{a_n b_m}$
$u(r)$	focal mode, normalized to $u(0) = 1$
f_0, T_0	fundamental beat frequency and period
k_s	frequency order of spot s, H_m group field of order m
D_d	Fourier coefficient of the intensity, beat order d
C	crest factor of the Radio Frequency (RF) signal per axis
$\eta,\ \alpha,\ P_\mathrm{s}$	diffraction efficiency, peak efficiency, saturation power

The amplitude ratios r_x, r_y are ratios for the optical Intensity. The spot and RF amplitudes therefore carry the square root:

$$a_n, b_m \in [\,\varrho, 1, \ldots, 1, \varrho\,], \qquad \varrho := \sqrt{r}. \tag{A.1}$$

A.1 The centering criterion

To better illuminate the center of the multi-tone profile, the intensity profile has to be symmetric regarding its center as the assumed maximum of the spatial probability density of the atom:

$$I(-\mathbf{r}, t) = I(\mathbf{r}, t) \quad \forall\, t \tag{A.2}$$

In terms of the electric field this realized by:

$$E(-\mathbf{r}, t) = e^{i\alpha(t)} E^*(\mathbf{r}, t), \tag{A.3}$$

with one and the same $\alpha(t)$ for the whole field. Each spot s of equation 2.35 can be dismantled into the two Acousto-Optical Deflector (AOD) tone indices (n, m):

$$E(\mathbf{r}, t) = \sum_{n,m} \sqrt{a_n b_m}\, u(\mathbf{r} - \mathbf{c}_{nm})\, e^{i2\pi(f_n + g_m)t}\, e^{i(\varphi_n + \psi_m)}. \tag{A.4}$$

The frequency for a spot created by one AOD is given by: $f_n = f_0 + W\frac{n}{N-1}$ and increases linearly with n. Hereby W is the frequency width. The profile itself has by construction already four symmetries, with the mirror index $\bar{n} = N - 1 - n$:

$$\text{The spot grid is centered:} \qquad \mathbf{c}_{\bar{n}\bar{m}} = -\mathbf{c}_{nm}, \tag{A.5}$$

$$\text{The spot profile is radially symmetric:} \qquad u(-\mathbf{r}) = u(\mathbf{r}), \tag{A.6}$$

$$\text{The amplitudes are symmetric:} \qquad a_{\bar{n}} = a_n, \qquad b_{\bar{m}} = b_m, \tag{A.7}$$

$$f_n \text{ increases linearly:} \qquad f_{\bar{n}} + f_n = F \qquad F = 2f_0 + W. \tag{A.8}$$

An equal frequency condition holds for g_m. Evaluating $E(-\mathbf{r}, t)$ and relabeling the sum by the mirror index results in:

$$E(-\mathbf{r}, t) = \sum_{\bar{n},\bar{m}} \sqrt{a_{\bar{n}} b_{\bar{m}}}\, u(-\mathbf{r} - \mathbf{c}_{\bar{n}\bar{m}})\, e^{i2\pi(f_{\bar{n}}+g_{\bar{m}})t}\, e^{i(\varphi_{\bar{n}}+\psi_{\bar{m}})},$$

Since $n, m \rightarrow \bar{n}, \bar{m}$ is a bijection of $\{0, ..., N-1\}$ on itself, the sum does not change by changing the indices back to n, m. Now the transformation for each component of the field can be performed. The single spot field does not change using its symmetries:

$$u(-\mathbf{r} - \mathbf{c}_{\bar{n}\bar{m}}) = u\big(-\mathbf{r} + \mathbf{c}_{nm}\big) = u\big(-(\mathbf{r} - \mathbf{c}_{nm})\big) = u(\mathbf{r} - \mathbf{c}_{nm}).$$

The amplitudes remain unchanged:

$$\sqrt{a_n b_m} = \sqrt{a_{\bar{n}} b_{\bar{m}}}.$$

The linearity of the frequencies together with the constant frequency offset F results in an additional time dependent phase for all spots:

$$e^{i2\pi(f_{\bar{n}}+g_{\bar{m}})t} = e^{i2\pi(F+G)t} \cdot e^{-i2\pi(f_n+g_m)t}.$$

After identifying all symmetries the field takes the form:

$$E(-\mathbf{r}, t) = e^{i2\pi(F+G)t} \sum_{n,m} \sqrt{a_n b_m} \cdot u(\mathbf{r} - \mathbf{c}_{nm}) \cdot\ e^{-i2\pi(f_n+g_m)t} e^{i(\varphi_{\bar{n}}+\psi_{\bar{m}})}.$$

For a direct comparison the complex conjugate field is calculated:

$$E^*(\mathbf{r}, t) = \sum_{n,m} \sqrt{a_n b_m} \cdot u(\mathbf{r} - \mathbf{c}_{nm}) \cdot e^{-i2\pi(f_n+g_m)t} e^{-i(\varphi_n+\psi_m)}. \tag{A.9}$$

Both sums run over the same basis functions with the same real coefficients and differ only by a phase per term. They are proportional, and hence Eq. (A.3) holds for $\alpha(t) = i[2\pi(F+G)t + \Theta]$, if and only if $e^{i(\varphi_{\bar{n}}+\psi_{\bar{m}})} = e^{i\Theta} e^{-i(\varphi_n+\psi_m)}$ for all n, m with a single constant Θ:

$$(\varphi_n + \varphi_{N_x-1-n}) + \big(\psi_m + \psi_{N_y-1-m}\big) = \Theta.$$

Since the first summand only depends on n and the second only on m, the sum is constant for every combination if and only if each summand is constant, resulting in the condition for a symmetric beam profile with $c_x, c_y \in \mathbb{R}$:

$$\boxed{\varphi_n + \varphi_{N_x-1-n} = c_x \ \ \forall n, \qquad \psi_m + \psi_{N_y-1-m} = c_y \ \ \forall m.} \tag{A.10}$$

A.2 Crest factor

The Crest factor of a RF signal $s(t)$ is calculated as the ratio of the maximum signal to its Root Mean Square (RMS) value:

$$C = \frac{\max_t |s(t)|}{\mathrm{rms}_t[s(t)]}. \tag{A.11}$$

The RF signal in a multi-tone setup is given by N different superimposed oscillations with amplitude a_n, frequency f_n and phase φ_n:

$$s(t) = \sum_{n=0}^{N-1} a_n \cos\left(2\pi f_n t + \varphi_n\right) = \mathrm{Re}[e^{i2\pi f_c t} A(t)] \tag{A.12}$$

The amplitude $A(t)$ can be expressed through a center frequency f_c:

$$A(t) = \sum_n a_n e^{i(2\pi(f_n - f_c)t + \varphi_n)} = |A(t)| e^{i\Theta(t)}. \tag{A.13}$$

So the RF signal takes the following form:

$$s(t) = \mathrm{Re}[|A(t)| e^{i[2\pi f_c t + \Theta(t)]}] = |A(t)| \cos\left(2\pi f_c + \Theta(t)\right). \tag{A.14}$$

The RMS is therefore given by:

$$\langle s(t)^2 \rangle = \frac{1}{2} \langle |A(t)|^2 \rangle, \tag{A.15}$$

which leads to an RMS value of:

$$\mathrm{rms}_t[s(t)] = \sqrt{\langle s(t)^2 \rangle} = \sqrt{\frac{1}{2} \langle |A(t)|^2 \rangle}. \tag{A.16}$$

As a result the Crest factor can be calculated with:

$$C = \frac{\max_t |s(t)|}{\mathrm{rms}_t[s(t)]} = \sqrt{2} \frac{\max_t |A(t)|}{\mathrm{rms}_t[A(t)]}. \tag{A.17}$$

For the RMS value the mean value vanishes for each pair of different frequencies, since the complex exponential averages out over one period:

$$\langle |A(t)|^2 \rangle = \sum_n a_n^2 + \sum_{n \neq m} a_n b_m \langle e^{i[2\pi(f_n - f_m)t + (\varphi_n - \varphi_m)]} \rangle = \sum_n a_n^2, \tag{A.18}$$

$$\mathrm{rms}_t |A(t)| = \sqrt{\langle |A(t)|^2 \rangle} = \sqrt{\sum_n a_n^2} \tag{A.19}$$

The lower bound for the Crest factor is found for a single tone in which maximum and RMS value coincide. The upper limit is calculated using the triangle inequality on $\max_t |A(t)|$:

$$\sqrt{2} \leq C \leq \sqrt{2} \frac{\sum_n a_n}{\sqrt{\sum_n a_n^2}} \xrightarrow{a_n \equiv 1} \sqrt{2N}. \tag{A.20}$$

For calculating the Crest factor for the cases $N = 3$ and $N = 4$ the curvature of the phases is defined as an auxiliary variable:

$$\psi = \varphi_1 - \frac{\varphi_0 + \varphi_2}{2}. \tag{A.21}$$

The Crest factor can be used to calculate the peak RF power if the average power P is given according to its definition in Equation A.11:

$$P_{\mathrm{peak}} = C^2 P_{\mathrm{avg}} \tag{A.22}$$

A power amplifier clips the instantaneous peak voltage and reaches compression. A condition to avoid compression can be formulated with $P_{\text{peak}} \leq P_{1\text{dB}}$, which results in:

$$P_{\text{avg}} \leq \frac{P_{1\text{dB}}}{C^2}. \tag{A.23}$$

With a 1 dB compression point of 40 dBm ≈ 10 W the resulting average power is given for the two Crest factors:

	C	C^2	$P_{\text{avg}} \leq P_{1\text{dB}}/C^2$
x axis, $N_x = 3$	2.4494	6.00	1.67 W
y axis, $N_y = 4$, $b = 98°$	2.1963	4.82	2.07 W

A.2.1 $N_x = 3$ and $N_y = 4$ tones

The amplitudes of the RF signal for three tones are given by:

$$a_0 = a_2 = \varrho := \sqrt{r_x}, \quad a_1 = 1 \tag{A.24}$$

For three tones the center frequency can be chosen as the second one $f_c = \bar{f} = f_1$. Together with the tone difference $d = f_n - f_c$ the RF amplitude can be expressed as:

$$A(t) = \varrho\, e^{\mathrm{i}(\varphi_0 - 2\pi d t)} + e^{\mathrm{i}\varphi_1} + \varrho\, e^{\mathrm{i}(\varphi_2 + 2\pi d t)}. \tag{A.25}$$

With a new parametrization for the phases using the defined phase curvature:

$$\varphi_0 - \varphi_1 = -\psi + \delta, \qquad \varphi_2 - \varphi_1 = -\psi - \delta, \qquad \delta = \tfrac{1}{2}(\varphi_0 - \varphi_2), \tag{A.26}$$

the amplitude takes the following form:

$$\begin{aligned} A(t)\, e^{-\mathrm{i}\varphi_1} &= \varrho\, e^{\mathrm{i}(-\psi + \delta - 2\pi d t)} + 1 + \varrho\, e^{\mathrm{i}(-\psi - \delta + 2\pi d t)} && \text{(A.27)} \\ &= \varrho\, e^{-\mathrm{i}\psi}\left[e^{\mathrm{i}(\delta - 2\pi d t)} + e^{-\mathrm{i}(\delta - 2\pi d t)}\right] + 1 && \text{(A.28)} \\ &= 2\varrho\, e^{-\mathrm{i}\psi} \cos\Theta + 1, \qquad \Theta = 2\pi d\,(t_\delta - t), \quad t_\delta = \frac{\delta}{2\pi d} && \text{(A.29)} \end{aligned}$$

The squared absolute value eliminates any left complex phase resulting in:

$$|A(t)|^2 = 4\varrho^2 \cos^2\Theta + 4\varrho \cos\psi\, \cos\Theta + 1. \tag{A.30}$$

The maximum lies at $\cos\Theta = \text{sign}(\cos\psi)$:

$$\max_t |A(t)| = \sqrt{4\varrho^2 + 4\varrho\,|\cos\psi| + 1}, \tag{A.31}$$

$$\text{rms}_t |A(t)| = \sqrt{2\varrho^2 + 1}, \qquad C_x(\psi) = \sqrt{2}\,\frac{\sqrt{4\varrho^2 + 4\varrho\,|\cos\psi| + 1}}{\sqrt{2\varrho^2 + 1}} \tag{A.32}$$

In the case of a symmetrical beam profile $\psi = 0$ holds:

$$\max_t |A(t)| = 2\varrho + 1 = \textstyle\sum_n a_n. \tag{A.33}$$

So for three tones the Crest factor is independent of the tone phases and always assumes its maximum value depending only on the amplitudes a_n. And for $\rho = \sqrt{0.97}$ the Crest factor is given by:

$$C_x = \sqrt{2}\frac{\sqrt{0.97}+1+\sqrt{0.97}}{\sqrt{0.97+1+0.97}} \approx 2.4494. \tag{A.34}$$

For calculating the Crest factor for four tones the same approach as before is used. Hereby the envelope frequency f_{env} is calculated with the frequency width W as $f_{\text{env}} = \frac{W}{N-1} = \frac{0.370\,\text{MHz}}{3} = 0.1233\,\text{MHz}$. Together with the center frequency f_c the following frequency parametrization is used:

$$f_n = f_0 + n f_{\text{env}}, \quad f_c = f_0 + \tfrac{3}{2} f_{\text{env}}, \qquad f_n - f_{\text{c}} = \left(n - \tfrac{3}{2}\right) f_{\text{env}} =: \hat{n}\, f_{\text{env}}. \tag{A.35}$$

With $\hat{n} \in \left\{-\frac{3}{2}, -\frac{1}{2}, +\frac{1}{2}, +\frac{3}{2}\right\}$ the exponent can be further simplified:

$$u := \pi f_{\text{env}} t \quad \Longrightarrow \quad 2\pi \hat{n} f_{\text{env}} t = 2\hat{n}u \in \{-3u,\, -u,\, +u,\, +3u\} \tag{A.36}$$

and $t \in [0, T_{\text{env}}) \;\leftrightarrow\; u \in [0, \pi)$ holds. With a reparameterization of the phases

$$\chi_n := \varphi_n - \tfrac{c}{2} \quad \Longrightarrow \quad \chi_{\text{a}} := \chi_3 = -\chi_0, \qquad \chi_{\text{i}} := \chi_2 = -\chi_1, \tag{A.37}$$

the parameters necessary for calculating the Crest factor are:

n	$\hat{n}$	a_n	φ_n	χ_n
0	$-\frac{3}{2}$	ϱ	0	$-c/2 = -\chi_{\text{a}}$
1	$-\frac{1}{2}$	1	b	$b - c/2 = -\chi_{\text{i}}$
2	$+\frac{1}{2}$	1	$c - b$	$c/2 - b = \chi_{\text{i}}$
3	$+\frac{3}{2}$	ϱ	c	$c/2 = \chi_{\text{a}}$

The optimization of the tone phases in regard of the Crest factor in chapter 4 results in $\varphi_n = [0°, 98°, 16°, 114°]$, so the reparameterization is $\chi_a = 57°$ and $\chi_i = -41°$. The amplitude can now be calculated with:

$$a_n e^{\mathrm{i}(2\hat{n}u+\varphi_n)} = e^{\mathrm{i}c/2}\, a_n e^{\mathrm{i}(2\hat{n}u+\chi_n)} \tag{A.38}$$

$$A(t)\, e^{-\mathrm{i}c/2} = \varrho\, e^{\mathrm{i}(-3u-\chi_{\text{a}})} + e^{\mathrm{i}(-u-\chi_{\text{i}})} + e^{\mathrm{i}(+u+\chi_{\text{i}})} + \varrho\, e^{\mathrm{i}(+3u+\chi_{\text{a}})} \tag{A.39}$$

Together with a trigonometric identity ($e^{\mathrm{i}x} + e^{-\mathrm{i}x} = 2\cos x$):

$$\varrho\left[e^{-\mathrm{i}(3u+\chi_{\text{a}})} + e^{+\mathrm{i}(3u+\chi_{\text{a}})}\right] = 2\varrho\cos(3u+\chi_{\text{a}}) \tag{A.40}$$

$$e^{-\mathrm{i}(u+\chi_{\text{i}})} + e^{+\mathrm{i}(u+\chi_{\text{i}})} = 2\cos(u+\chi_{\text{i}}), \tag{A.41}$$

the amplitude takes the form:

$$A(t)\, e^{-\mathrm{i}c/2} = 2\varrho\cos(3u+\chi_{\text{a}}) + 2\cos(u+\chi_{\text{i}}) \quad \in \mathbb{R}. \tag{A.42}$$

Doing a substitution of the used variable $u' := u + \chi_{\text{i}}$:

$$u + \chi_{\text{i}} = u', \tag{A.43}$$

$$3u + \chi_{\text{a}} = 3u' - 3\chi_{\text{i}} + \chi_{\text{a}} = 3u' + \gamma, \tag{A.44}$$

gives the wanted form of the amplitude

$$A(t)\, e^{-\mathrm{i}c/2} = 2\varrho\cos(3u'+\gamma) + 2\cos(u'), \tag{A.45}$$

$|A(t)|$ has a period of π since for the working point holds:

$$\gamma = \chi_\mathrm{a} - 3\chi_\mathrm{i} = 3b - c = 57^\circ - 3\cdot(-41^\circ) = 180^\circ \tag{A.46}$$

and the cosine is antisymmetric:

$$u' \to u' + \pi: \quad \cos u' \to -\cos u', \quad \cos(3u' + \gamma) \to -\cos(3u' + \gamma) \tag{A.47}$$

Using the condition of the working point $\gamma = \pi$ simplifies the amplitude:

$$A(t)\, e^{-\mathrm{i}c/2} = 2\cos(u') - 2\varrho\cos(3u'). \tag{A.48}$$

To find its maximum for the Crest factor, several trigonometric identities [29] are used:

$$\cos(3u') = \cos(2u' + u') = \cos(2u')\cos(u') - \sin(2u')\sin(u') \tag{A.49}$$

$$= (2\cos^2(u') - 1)\cos(u') - 2\sin^2(u')\cos(u') \tag{A.50}$$

$$= 4\cos^3(u') - 3\cos(u'). \tag{A.51}$$

With the substitution $v := \cos u' \in [-1, 1]$ the function to be maximized becomes:

$$G(v) := A(t)\, e^{-\mathrm{i}c/2} = 2v - 2\varrho(4v^3 - 3v) = (2 + 6\varrho)\, v - 8\varrho\, v^3, \tag{A.52}$$

since $|A(t)| = |G(v)|$ holds true. Because $G(v)$ is antisymmetric and just $|G(v)|$ is of interest, only $v :\in [0, 1]$ is considered. The maximum is then calculated with the root of the first derivative:

$$G'(v) = (2 + 6\varrho) - 24\varrho\, v^2 \tag{A.53}$$

$$G'(v_*) = 0: \quad v_*^2 = \frac{2 + 6\varrho}{24\varrho} = \frac{1 + 3\varrho}{12\varrho}, \tag{A.54}$$

The found root is in fact a maximum:

$$G''(v) = -48\varrho v < 0, \qquad v_* \le 1 \;\Leftrightarrow\; \varrho \ge \tfrac{1}{9}. \tag{A.55}$$

The maximum value is then calculated as

$$G(v_*) = v_*\big[(2 + 6\varrho) - 8\varrho v_*^2\big]. \tag{A.56}$$

Together with $8\varrho v_*^2 = 8\varrho\cdot\frac{1+3\varrho}{12\varrho} = \frac{2}{3}(1+3\varrho)$ and $(2+6\varrho) - \frac{2}{3}(1+3\varrho) = \frac{4}{3}(1+3\varrho)$ the maximum is:

$$G(v_*) = \tfrac{4}{3}(1 + 3\varrho)\, v_* = \tfrac{2}{3}\,\frac{(1 + 3\varrho)^{3/2}}{\sqrt{3\varrho}}. \tag{A.57}$$

So the Crest factor for four tones with the optimized phases can then be calculated.

$$\boxed{\max_t|A(t)| = \frac{2}{3}\,\frac{(1 + 3\varrho)^{3/2}}{\sqrt{3\varrho}}, \qquad C_y = \sqrt{2}\,\frac{\frac{2}{3}(1 + 3\varrho)^{3/2}/\sqrt{3\varrho}}{\sqrt{2\varrho^2 + 2}} \approx 2,1963} \tag{A.58}$$

A.3 Power of a normalized profile

For calculating the pulse area θ of the multi-tone profile, the power of a normalized profile $\tilde{P}_{\text{prof}}$ has to be calculated. The profile can then be scaled to the desired power P using the scaling factor s, such that $P = s\tilde{P}_{\text{prof}}$.
A single spot has the form $g_s = A_s\, u(\mathbf{r} - \mathbf{c}_s)$ with the field amplitude $A_s = \sqrt{a_{x,i} a_{y,j}}$. The intensity weight of a spot the following is redefined as:

$$a_s \equiv A_s^2 = a_{x,i}\, a_{y,j}. \tag{A.59}$$

The optical power of a single spot can be calculated as

$$\int g_s^2 \,\mathrm{d}^2 r = a_s P_1, \qquad P_1 = \int |u|^2 \mathrm{d}^2 r. \tag{A.60}$$

For further calculations the used vector notation is: $r = |\mathbf{r}|$, $q = |\mathbf{q}|$, $d = |\mathbf{d}|$. The mode functions (Gaussian and Airy) are radially symmetric, so u is written as a function of the scalar radius, $u(r) \equiv u(|\mathbf{r}|)$, and the same holds for $\tilde{u}(q)$ and for the overlap $O(d)$. Calculating the power of a Gaussian spot results in:

$$P_1^{\mathrm{G}} = \int_0^\infty e^{-2r^2/w_0^2}\, 2\pi r \,\mathrm{d}r = \frac{\pi w_0^2}{2} \int_0^\infty e^{-x}\,\mathrm{d}x = \frac{\pi w_0^2}{2}. \tag{A.61}$$

For one Airy profile, with $x = kr$ and the integral $\int_0^\infty J_\nu^2(x)\,\mathrm{d}x/x = 1/(2\nu)$ [30], the power is:

$$P_1^{\mathrm{A}} = \int_0^\infty \left(\frac{2J_1(kr)}{kr}\right)^2 2\pi r \,\mathrm{d}r = \frac{8\pi}{k^2} \int_0^\infty \frac{J_1^2(x)}{x}\,\mathrm{d}x = \frac{8\pi}{k^2} \cdot \frac{1}{2} = \frac{4\pi}{k^2}, \tag{A.62}$$
$$k = \frac{3.8317}{1.483\, w_0}.$$

The Airy spot carries $4\pi/k^2 \big/ (\pi w_0^2/2) = 1.20$ times the power of a Gaussian spot of the same $1/e^2$ width, because of its rings. The time average of the coherent sum, as discussed in chapter 2 is given by:

$$\langle \tilde{I}(\mathbf{r}, t)\rangle_t = \sum_s g_s^2(\mathbf{r}) + 2 \sum_{\substack{s<s' \\ k_s = k_{s'}}} g_s(\mathbf{r}) g_{s'}(\mathbf{r}) \cos(\phi_s - \phi_{s'}), \tag{A.63}$$

because a pair of spots with $k_s \neq k_{s'}$ oscillates at $(k_s - k_{s'})f_0$ and averages to zero over T_0, while a degenerate pair of spots does not oscillate at all. Integrating term by term over the plane gives:

$$\tilde{P}_{\text{prof}} = \sum_s a_s\, P_1 + 2 \sum_{\substack{s<s' \\ k_s = k_{s'}}} A_s A_{s'} \cos(\phi_s - \phi_{s'}) \underbrace{\int u(\mathbf{r} - \mathbf{c}_s) u(\mathbf{r} - \mathbf{c}_{s'})\,\mathrm{d}^2 r}_{O(d_{s,s'})}, \tag{A.64}$$

with $d \equiv d_{s,s'} = |\mathbf{c}_s - \mathbf{c}_{s'}|$ being the distance between the two spots. Calculating the power of the normalized profile reduces to evaluating the power of the single spots and the overlap integral $O(d)$. For Gaussian spots the overlap can be calculated with the midpoint $\mathbf{m} = \frac{1}{2}(\mathbf{c}_s + \mathbf{c}_{s'})$ and the Gaussian integral [29]:

$$e^{-\frac{(\mathbf{r}-\mathbf{c}_s)^2}{w_0^2}}\, e^{-\frac{(\mathbf{r}-\mathbf{c}_{s'})^2}{w_0^2}} = e^{-\frac{d^2}{2w_0^2}}\, e^{-\frac{2(\mathbf{r}-\mathbf{m})^2}{w_0^2}},$$

$$O^{\mathrm{G}}(d) = \frac{\pi w_0^2}{2}\, e^{-d^2/2w_0^2} = P_1^{\mathrm{G}}\, e^{-d^2/2w_0^2} = P_1^{\mathrm{G}} u(d). \tag{A.65}$$

For the Airy mode the integral is calculated in the Fourier space. The Fourier transform of a uniform illuminated circular disk is proportional to the Airy function [30]:

$$\frac{1}{(2\pi)^2} \int_{|\mathbf{q}|<k} e^{i\mathbf{q}\cdot\mathbf{r}}\, \mathrm{d}^2 q = \frac{k^2}{4\pi}\, \frac{2J_1(kr)}{kr} = \frac{k^2}{4\pi}\, u(r), \qquad r = |\mathbf{r}|, \tag{A.66}$$

where the left side is an integral over the vector $\mathbf{q}$ and the right side depends only on the length r. Based on this result the contrary Fourier transform is given by:

$$\tilde{u}(q) = \int u(|\mathbf{r}|)\, e^{-i\mathbf{q}\cdot\mathbf{r}}\, \mathrm{d}^2 r = \frac{4\pi}{k^2}\, \Theta(k-q)\,, \qquad q = |\mathbf{q}|, \tag{A.67}$$

Θ is the Heaviside step function that has the value one inside the cutoff of the largest possible wave vector $k = 2\pi\,\mathrm{NA}/\lambda$ and zero outside. With the Fourier transform the shifted Airy spot can be expressed by:

$$u(|\mathbf{r}-\mathbf{d}|) = \frac{1}{(2\pi)^2} \int \tilde{u}(\mathbf{q}) e^{i\mathbf{q}\mathbf{r}} e^{-i\mathbf{q}\mathbf{d}} d^2 q,$$

and the overlap becomes:

$$O^{\mathrm{A}}(d) = \int u(|\mathbf{r}|)\, u(|\mathbf{r}-\mathbf{d}|)\, \mathrm{d}^2 r = \frac{1}{(2\pi)^2} \int |\tilde{u}(q)|^2\, e^{i\mathbf{q}\cdot\mathbf{d}}\, \mathrm{d}^2 q. \tag{A.68}$$

The result depends only on the distance $d = |\mathbf{d}|$. With $\Theta^2 = \Theta$ applied, the overlap is given by:

$$O^{\mathrm{A}}(d) = \frac{1}{(2\pi)^2} \left(\frac{4\pi}{k^2}\right)^2 \frac{2\pi k J_1(kd)}{d} = \frac{8\pi\, J_1(kd)}{k^3 d} = \frac{4\pi}{k^2} \cdot \frac{2J_1(kd)}{kd} = P_1^{\mathrm{A}}\, u(d). \tag{A.69}$$

So in both cases the overlap of two spots is calculated as the power of the single spot profile multiplied with the mode function evaluated at their respective distance.
The power of the normalized profile composed of Airy profiles is given by:

$$\tilde{P}_{\mathrm{prof}} = \frac{4\pi}{k^2} \sum_s a_s + \frac{8\pi}{k^2} \sum_{\substack{s<s' \\ k_s = k_{s'}}} A_s A_{s'}\, \cos(\phi_s - \phi_{s'}) u(d_{s,s'}). \tag{A.70}$$

For the right choice of phases the overlap can vanish and only the sum of the single spots remains.

Bibliography

[1] P. W. Shor, *Algorithms for quantum computation: discrete logarithms and factoring*, in: *Proceedings 35th annual symposium on foundations of computer science*, Ieee (1994), 124–134.

[2] D. A. Steck, *Rubidium 85 D Line Data, revision 2.3.4, 8 August 2025*, URL: http://steck.us/alkalidata (visited on 17/09/2026).

[3] L. Pause, L. Sturm, M. Mittenbühler, S. Amann, T. Preuschoff, D. Schäffner, M. Schlosser and G. Birkl, *Supercharged two-dimensional tweezer array with more than 1000 atomic qubits*, *Optica* **11**, 222–226 (2024).

[4] M. Schlosser, S. Tichelmann, D. Schäffner, D. O. de Mello, M. Hambach, J. Schütz and G. Birkl, *Scalable Multilayer Architecture of Assembled Single-Atom Qubit Arrays in a Three-Dimensional Talbot Tweezer Lattice*, *Phys. Rev. Lett.* **130**, 180601 (2023).

[5] S. Bickel, *Ramanlaser für Ein-Qubit-Quantengatter: Entwicklung eines Hochleistungssystems mitgeringem Phasenrauschen*, Masterthesis, Technische Universität Darmstadt (2024).

[6] D. Hagn, *Wiederinbetriebnahme eines Raman-Lasersystems für Zwei-Photonen-Anregungen*, Thesis-Proposal, Technische Universität Darmstadt (2026).

[7] A. Thiel, *Optischer Aufbau für die kohärente Anregung von atomaren Quantenbits in einem 2D Register aus Atomfallen*, Bachelorthesis, Technische Universität Darmstadt (2024).

[8] C. Berghöfer, *Globale Adressierung für zustandsselektives Auslesen von zwei-dimensionalen Qubit-Registern*, Bachelorthesis, Technische Universität Darmstadt (2025).

[9] *FBS®-R Top Hat Beam Shaper*, URL: https://topag.de/wp-content/uploads/2025/05/FBS-Round-Top-Hat-Shaper_TOPAG.pdf.

[10] M. Mittenbuehler, *Reactive Real-Time Synthesis of Multiple Tweezers for Parallelized Atom Transport*, Masterthesis, Technische Universität Darmstadt (2024).

[11] D. P. DiVincenzo, *The physical implementation of quantum computation*, *Fortschritte der Physik: Progress of Physics* **48**, 771–783 (2000).

[12] D. A. Steck, *Quantum and Atom Optics*, University of Oregon (2026).

[13] L. Pause, *A New Setup for Scaling Up Microlens-Based Individual-Atom Quantum Processors*, PhD thesis, Technische Universität Darmstadt (2023).

[14] T. Schreiber, *Demonstration of Quantum Gate Operations and Quantum Sensing on a Scalable System Based on Neutral Atoms*, PhD thesis, Technische Universität Darmstadt (2024).

[15] M. Domack, *Single-site addressed state-manipulation and Rydberg excitation on neutral atoms as building blocks for a CNOT gate*, Masterthesis, Technische Universität Darmstadt (2023).

[16] I. C. Chang, *Acousto-optic devices and applications*, in: *Handbook of Optics*, **2**, McGraw-Hill (1995).

[17] A. Korpel, *Acousto-optics — a review of fundamentals*, *Proceedings of the IEEE* **69**, 48–53 (1981).

[18] J. Lautenschläger, *Präparation und Einzelplatz- Adressierte-Raman-Anregung in einem 2D neuralen Atomegitter bei 795nm*, Masterthesis, Technische Universität Darmstadt (2022).

[19] U. Umhofer, E. Jäger and C. Bischoff, *Refractive and diffractive laser beam shaping optics*, *Laser Technik Journal* **8**, 24–27 (2011).

[20] J. W. Goodman, *Introduction to Fourier Optics*, 4th edition, W. H. Freeman, New York (2017).

[21] *Test Sheet DTSXY-400-800*, AA Opto-Electronic.

[22] R. Decruyenaere, C. Tanghe, S. Van Wellen and K. Van Acoleyen, *Fast projections of two-dimensional light patterns using acousto-optical deflectors*, *arXiv preprint arXiv:2604.19421* (2026).

[23] M. Born and E. Wolf, *Principles of Optics: Electromagnetic Theory of Propagation, Interference and Diffraction of Light*, 7th edition, Cambridge University Press (1999).

[24] *FBSR installation instructions*, TOPAG Lasertechnik.

[25] D. Hagn, *Multitone Simulation*, GitHub repository, GitHub (2026), URL: https://github.com/TU-Darmstadt-APQ/Multitone_Simulation.

[26] M. Friese, *Multitone signals with low crest factor*, *IEEE Transactions on Communications* **45**, 1338–1344 (1997).

[27] W. Demtröder, *Experimentalphysik 2 - Elektrizität und Optik*, 6th edition, Springer, Berlin, Heidelberg (2008).

[28] E. J. Robertson, N. Šibalić, R. M. Potvliege and M. P. A. Jones, *ARC 3.0: An expanded Python toolbox for atomic physics calculations*, *Computer Physics Communications* **261**, 107814 (2021).

[29] NIST Digital Library of Mathematical Functions, *Chapter 4: Elementary Functions*.

[30] NIST Digital Library of Mathematical Functions, *Chapter 10: Bessel Functions*.

Internet sources were last accessed on November 3, 2026.

Erklärung zur Abschlussarbeit gemäß § 22 Abs. 7 APB TU Darmstadt

Hiermit erkläre ich, Daniel Hagn, dass ich das vorliegende Proposal gemäß § 22 Abs. 7 APB der TU Darmstadt selbstständig, ohne Hilfe Dritter und nur mit den angegebenen Quellen und Hilfsmitteln angefertigt habe. Ich habe mit Ausnahme der zitierten Literatur und anderer in der Arbeit genannter Quellen keine fremden Hilfsmittel benutzt. Die von mir bei der Anfertigung dieser wissenschaftlichen Arbeit wörtlich oder inhaltlich benutzte Literatur und alle anderen Quellen habe ich im Text deutlich gekennzeichnet und gesondert aufgeführt. Dies gilt auch für Quellen oder Hilfsmittel aus dem Internet.
Diese Arbeit hat in gleicher oder ähnlicher Form noch keiner Prüfungsbehörde vorgelegen.
Mir ist bekannt, dass im Falle eines Plagiats (§ 38 Abs. 2 APB) ein Täuschungsversuch vorliegt, der dazu führt, dass die Arbeit mit 5,0 bewertet und damit ein Prüfungsversuch verbraucht wird. Abschlussarbeiten dürfen nur einmal wiederholt werden.

Darmstadt, 03.11.2026

Daniel Hagn